

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan  
(County)

Located in:

Corner Code #

1. Public Land Survey

4N 11W

M-6 (E 1/4, 13)

Leighton Twp.

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

1995 DEC 14 PM 2:34  
REGISTER OF DEEDS  
ALLEGAN COUNTY  
Register of Deeds Stamp & File Number

**SURVEY & REMONUMENTATION**

APR 29 1996

**COMMISSION**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	15	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Steven Koerber in a field survey on August 31, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented; recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- M-6 GLO Post set  
Lucius Lyon DS. 1826  
Sugar 7 S 39 W 32  
Sugar 8 N 51 W 37
- 1. Exxel Eng. notes  
Found 1 1/4" Iron  
no witnesses to iron pipe but mention is made of the iron pipe in 1987 witnesses of A-6, T 4N, R10W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-6 Found 1 1/4" Iron Pipe  
Capped rerod North 2.67'  
Solid Iron rod North 3.90'
- During the cutting phase of road construction, below the 1 1/4" IP Found 3/4" Iron rod next to 16"x16"x10" tapering toward the top, stone. The iron rod was 0.03' So. and 0.10' W. of the 1 1/4" IP which was above the rod The top of the Stone was 0.2' East and 0.2' South of the 3/4" iron rod (which makes it 0.23'S. & 0.1' East of the witnessed 1 1/4" IP)  
The Stone position was remonumented.

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.  
Peer Group approval September 12, 1995

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 9-12-95  
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-6 Replaced Stone with Allegan Co. Mon. ( 3/4" x 24" Iron Rod with cap)  
Set 3/4" x 24" Iron rod with Allegan Co. Remonumentation witness cap S 45° E 65.19'  
Set 3/4" x 24" Iron rod with Allegan Co. Remonumentation witness cap N 50° E 60.18'  
Set 3/4" x 24" Iron rod with Allegan Co. Remonumentation witness cap N 45° W 50.55'  
Set 3/4" x 24" Iron rod with Allegan Co. Remonumentation witness cap S 50° W 44.46'  
A-6.Thornapple Twp., Barry County, corner is North 2.90'

Signed by [Signature] Date 11-13-1995  
Surveyor's Michigan License No. 39085

0005 PAGE 241

STATE OF MICHIGAN  
STEVEN C. KOERBER  
PROFESSIONAL SURVEYOR  
NO. 39085  
FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN. 1993  
REVISOR M.A. J.