

**SURVEY
REMONUMENTATION**

APR 29 1999

Allegan County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Allegan</u> (County)	Located In:	Corner Code #
	4N 11W	M-12 (E 1/4, Sec.36)
1. Public Land Survey	T___ R___	Leighton Twp.
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

LIBERO 006 PAGE 81

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Steven Koerber, in a field survey on May 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-12 GLO Set Post, Lucius Lyons DS, 1826
W. Oak 18 S54W 22
R. Oak 30 N45W 67

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


M-12 Nothing found at corner position
Set corner monument 1/2 way and on line between M-11 and M-12
Measure to M-11 2653.40'
Measure to M-13 2653.40'

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED AUG 11, 1998
COUNTY REP. [Signature]

And is accepted as a careful and faithful reestablishment of the position of the original corner.
Peer Group approval August 11, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12 Set Allegan Co. Mon. (3/4" x 24" Iron Rod with cap)
PK Nail in top wood guard post S60°W 22.25'
PK Nail in top wood guard post N35°W 31.45'
PK Nail in top wood guard post N45°E 28.47'
PK Nail in top wood guard post S40°E 21.88'
1" iron rod in Mon. box North 5.30' (W 1/4 cor Sec 31-4-10)



Signed by [Signature]
Surveyor's Michigan License No. 39085

Date 10-10-1998