

**Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Allegan Co.</u> <small>(County)</small>	Located in: <u>Dorr</u> Twp.	Corner Code <u>B-13</u>
1. Public Land Survey	T <u>4N</u> R <u>12W</u>	<u>B-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
3. Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

1995 DEC 14 PM 2:33
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
 REGISTER OF DEEDS STAMP & FILE NUMBER

**SURVEY &
REMONUMENTATION**

APR 29 1996

COMMISSION

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert J. Jonker in a field survey on December 13, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereto as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O., West 40 ch. set 1/4 sec. post, Page 258
 Beech 16 N 36 W 22 Lucius Lyon, D.S., 1831
 Beech 17 N 58 E 39

B-13, Ratekin, 1982, recorded by LCRC in L. 3, P. 211
 Found stone, set 3/4" iron on E. side and bent iron over stone to West
 P. pole North 57.56'
 C/L North gas valve S 60° E 91.58'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1' x 1/2' stone with bent 3/4" solid pin angled over the C/L of the top of the stone.


Found by witnesses listed in "A" above for L.C.R.C. APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 12-14-95
 COUNTY REP. Robert J. Jonker

This monument is accepted by myself as a careful perpetuation of the position of the corner.

Peer group approved on 12-14-95.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced with 3/4" x 36" standard capped Allegan County monument in C/L gravel
 C/L top S. gas valve S 60° E 93.20' road.
 SW corner garage (brick) N 30° E 108.95'
 A/C tag on W. side P. pole N 05° E 57.86'
 A/C tag on S. side 10" W. Ch. S 55° W 89.80'
 A/C tag on W. side 8" Sas. S 10° E 58.28'
 N 1/4 corner, Sec. 6, T3N, R12W East 18.06'



Signed by Robert J. Jonker
 JONKER LAND SURVEYS, P.C. 21572
 Surveyor's Michigan License No. _____

Date December 14, 1994

0005 PAGE 203