

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION


For corners in
Allegan
(County)

Allegan County Remonumentation LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

	Located In: Dorr Twp.	Corner Code #
1. Public Land Survey	T 4N R 12W	C-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS
 ALLEGAN COUNTY
 1994 DEC 16 AM 9:56
 FILED
 Register of Deeds Stamp & File Number

I, Robert Jonker, in a field survey on August 06, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:



NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


A. Description of original monument and accessions and/or subsequent restoration:
 G.L.O. survey, T5N, R12W G.L.O. survey, T4N, R12W, 1831 Corner common with T5N, R12W.
 Beech 13", N 52° W 18' Intersect N. boundary at post
 Beech 7", N 27° E 36'
 L.C.R.C., L. 2, Pg.163, Ratekin, 1973, Iron L.C.R.C., L.2, Pg.310, C.P.Co., 1974
 T.pole S 60° W 46'2" Fd. 3/8" rebar
 P.pole S 45° E 36.7' SW cor. stone N 45° E 62.95'
 Sign post N 45° W 40.5' 18" Maple S 45° W 55.07' (OVER)
 28" Maple S 60° W 55.2' L.C.R.C., L.2, Pg.317, 1974, Nederveld
 PK T.pole SW 46.61' PK T.pole NW 43.29'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 4" Cast Iron Monument (Harrison) set by Kent County per L. 2, Pg.310, 1974
 SW cor. store (now hse) NE 62.95'
 Per L.2, Pg.317, 1974
 T.pole SW 46.61'
 T.pole NW 43.29'
 P.pole SSE 37.17'
 PK P.pole SSE 37.17'
 C/L 22nd St W. 3.5'
 C/L 108th St N-S 0.0'

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 8-9-94
 COUNTY REP. Rich L. [Signature]

C. Description of monument for corner and accessions established to perpetuate locating the position of the

4" Cast Iron Monument
 Kent Co. N&T on NE side G.pole Az. 310° 43.17'
 Kent Co. N&T on NW side T.pole Az. 240° 46.69'
 Kent Co. N&T on W. side P.pole Az. 150° 37.07'
 SW corner house Az. 40° 62.98'
 C/L of E-W pavement, South 1'
 C/L of N-S pavement, West 5 1/2'



Accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by Robert J. Jonker Date August 09, 1994
 JONKER LAND SURVEYS 21572
 Surveyor's Michigan License No.

189-0005 PAGE 073

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

Allegmt

A. (continued)

Old County Surveyor notes call for a stone 18" x 12" x 10", 1869?

C-13, T5N, R12W

Recorded by LCRC's #1306, 1574, 4543

LCRC #1306, 1979, Nederveld

Found $\frac{1}{2}$ " solid iron by previous wit.

LCRC #1574, 1981, Jonker

Solid iron over stone - set K.C. monument for remonumentation.

LCRC #4643, Bueche, 1988

Remon. maint.