

**Allegan County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Allegan Co.</u> <small>(County)</small>	Located In: <u>Dorr</u> Twp.	Corner Code # <u>C-13</u>
1. Public Land Survey	T <u>4N</u> R <u>12W</u>	<u>C-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTERED  
 1995 DEC 14 PM 2:33  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY, MICHIGAN

FILED

Register of Deeds Stamp & File Number

**SURVEY &  
REMONUMENTATION  
COMMISSION**

APR 29 1996

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21	22	23	24			
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Robert J. Jonker in a field survey on December 13, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O., 80 ch., set post cor. Sec. 31 & 32 Page 258  
 Beech 9 N 55 W 32 Lucius Lyon D.S., 1831  
 Maple 20 N 17 E 14

(over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2' x 1 1/2' stone with "X" cut on top, with iron bent over the top.  
 Found by all witnesses listed on the reverse side.

APPROVED REMONUMENTATION CORNER  
 P.A. 343 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 12-14-95  
 COUNTY REP. Robert J. Jonker

This monument is accepted by myself as a careful and faithful perpetuation of the position of the corner.

Peer group approved on 12-14-95.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced with 3/4" x 36" standard capped Allegan County monument in gravel road.  
 A/C tag on S. side P. pole East 80.88'  
 A/C tag on W. side 36" Maple S 20° W 56.92'  
 A/C tag on E. side P. pole N 20° W 68.12'  
 A/C tag on W. side P. pole N 40° E 153.66'  
 A/C tag on E. side 16" Maple S 15° W 94.58'  
 NE cor. Sec. 6, T3N, R12W, East 13.2'

(over for Sheet 2)

Signed by Robert J. Jonker Date December 14, 1994  
 JONKER LAND SURVEYS, P.C. 21572  
 Surveyor's Michigan License No. \_\_\_\_\_



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 20, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983

0005 PAGE 204

1 OF 2

Old County Surveyor notes, no date, calls for a stake and stone

Ratekin - 1979, 3/4" pipe over stone  
30" Maple S 15° W 56.7'  
PK W. side P. pole N 40° E 152.94'  
PK NE side P. pole N 40° W 67.81'  
1/2" pipe over stone East 13.98'±  
C/L 22nd Street East 4'±

Jonker - 1989, Iron angle over large stone