

APR 25 1995

COMMISSION

Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan (County)	Located in: Dorr Twp.	Corner Code #
1. Public Land Survey	T 4N R 12W	D-1
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REGISTER OF DEEDS
 ALLEGAN COUNTY MICHIGAN
 1994 DEC 16 AM 9:56
 FILED

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert Jonker, in a field survey on August 06, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 NOT SET IN G.L.O. survey, however corner is common with T5N, R12W, wit. follows:
 Beech 21 N 53° W 25
 Lynn 23 N 37° E 31
 Old survey notes call for a stone
 8 x 8 x 6 - 1859 (E.Strong, Dep.Surv.)
 LCRC, L.2, P.310, Duane Ankrom, 1974
 Found "T" Iron
 LCRC, L.2, P.398, Nederveld, 1975
 "T" Iron per old wit.
 1980, Ratekin
 Found "T" Iron, checks witnesses

(OVER)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

Found Kent County monument per LCRC #4613 (Kent County).

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 8-9-94
 COUNTY REP. Richard Van Orden

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 4" Cast Iron (Harrison Monument)
- A.C. Tag E. side 26" Chestnut Az. 210° 70.52'
- A.C. Tag W. side 9" Basswood Az. 20° 101.39'
- A.C. Tag E. side 24" Maple Az. 165° 79.50'
- "X" cut on top curb Az. 320° 40.39'
- C/L pav't. to North of 4'± West
- C/L gravel to South is 4'± West
- C/L E-W pav't. is 1½'± South



Signed by Robert J. Jonker Date December 02, 1994
 JONKER LAND SURVEYS, P.C.
 Surveyor's Michigan License No. 21572

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1974
 REVISED MAY 14, 1975
 REVISED JAN., 1983

Allgon

Section "A" continued:

Recorded in Kent County @ D-13 by the following LCRC's:

#1306

#1577

#4613

LCRC #1306, Nederveld, 1979

Found "T" iron by previous witnesses

LCRC #1577, Jonker, 1981

Found "T" iron, set Harrison monument for Kent County Remonumentation

LCRC #4613, Bueche, 1988, Harrison monument for Kent County Maint.