

**Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Allegan
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>12W</u>	<u>D-13 (S$\frac{1}{2}$, 32)</u> <u>Dorr Twp.</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
 97 JAN 22 AM 1:22
 FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

I, John C. Bueche, in a field survey on October 1, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-13 GLO Jonker, 1984
 Lucius Lyon, D.S. Old fence & tree line N
 1831 Set 1/2" capped rered with old oak stake
 Set qr. sec. post Set spk. on S side PP N 85 W 148.5'
 Birch 16 N 25 E 9 C/L fence intersection to S, E 6.5'
 Beech 8 N 39 W 17 Set PK Nail in E side 8" Ash N 10 E 40.59'
 Set PK Nail in NE side 15" Oak N 45 W 64.38'
 Sq. spk. on W side 14" Sassafras S 15 E 39.09'
 Pointed stone East 6.6' (W to SW 2648.63', E to SE 2657.44')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 Found capped Jonker iron Area has been cleared 40' N & S of cor.
 Spk. on S side PP N 85 W 148.5'±
 Stump 15" Oak N 45 W 64.4'±
 Stump 14" Sassafras S 15 E 39'±
 On old fence line N
 Old fence line South, East 7'
 Power line E-W, North 2.5'
 Found stone East 6.6' mea. W to SW 2649.12'
 No fences at corner E to SE 2657.46'

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 10-8-96
 COUNTY REP. John C. Bueche


And is accepted as a careful and faithful perpetuation of the position of the original corner

Approved by Allegan Peer Group 10/8/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 Replaced capped rered with 3/4" x 36" pin with Allegan Cap
 Nail & Allegan Co. Remon. Tag in E side 10" Sassafras S 10 E 47.18'
 Nail & Allegan Co. Remon. Tag in W side 20" Oak N 20 W 77.14'
 Nail & Allegan Co. Remon. Tag in W side 12" Ash N 12 E 97.29'
 Nail & Allegan Co. Remon. Tag in E side 12" Poplar N 41 E 78.84'
 Spk. in S side PP N 85 W 148.22'
 Allegan Co. Mon. East 6.6' (N 1/4 Sec. 5 Hopkins Twp.)

Signed by John C. Bueche Date 10-6-96
 Surveyor's Michigan License No. 13027



FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN. 26, 1971
 REVISED MAY 14, 1979
 REVISED JAN., 1983