

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

For corners in

**Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

<u>Allegan</u> (County)	Located in: Dorr Twp.	Corner Code #/
1. Public Land Survey	T4N R12W	E-1
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REGISTER OF DEEDS
 ALLEGAN COUNTY MICHIGAN
 1994 DEC 16 AM 9:56
 FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert Jonker, in a field survey on August 06, 19 94
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post for corner Sec. 32 & 33, T5N, R12W Intersect N. boundary at post
 Sugar 15, N 38° E 17 T4N, R12W, @ 77.00 ch.
 Sugar 24, N 43° W 56 No witnesses noted.

Old Co. Surveyor notes call for
 stone, 18 x 12 x 10

LCRC, L.2, P.310, Ankron, 1974, C.P. Co.
 Found 1" pipe
 6" Maple S 75° E 60.51'
 St. sign N 20° E 42.17'
 MBT pole N 70° E 61.30'

(OVER)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 4" cast iron monument (set by Kent County)

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 8-9-94
 COUNTY REP. Robert J. Jonker

Accepted as a careful and faithful perpetuation of the position of the
 original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

4" CAST IRON monument (Harrison)
 "X" cut on top of curb Az. 330° 40.50'
 PK Nail on NW side corner fce. post Az. 55° 44.14'
 A.C. Tag NW triple 10" Elm Az. 215° 48.40'
 A.C. Tag N. triple 3" Elm Az. 120° 57.43'
 On C/L on pav't to E-W road
 C/L to North is 4' West



Signed by Robert J. Jonker Date December 02, 1994
 JONKER LAND SURVEYS, P.C. 21572
 Surveyor's Michigan License No. _____

0005 PAGE 069

Sheet 1 of 2

Allegheny

Section "A" continued:

E-13, T5N, R12W, Kent County
LCRC #2304, 4426, 4614

LCRC #2304, 1981, Nederveld, Kent County monument
LCRC #4426, 1986, Jonker, Reset Kent County monument after construction
LCRC #4616, 1988, Bueche, Remon. Maint.

Prior to 1981
Kent County wit. map - no date

1/2" Iron
MBT NE 36.49'
3/4" iron South 26.13'
C.P. SW 64.64'
MBT NW 46.69'

Prior to wit. map
Long stone
Fence post NE 37.5'
Fence post SE 24.9'
Leaded stone S 33'