

COPY

Allegan County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION  
For corners in  
Allegan  
(County)

	Located In:	Corner Code #
1. Public Land Survey	T 4N R 12W * E-13 (SE, 32) T _____ R _____ T 3N R 12W * E-1 (NE, 5) T _____ R _____	Dorr Twp. Hopkins Twp.
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	

97 JAN 22 PM 1:23  
FILED  
Allegan County, Michigan  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John C. Bueche, in a field survey on October 1, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	13	12	11	10	9	8	7	6	5	4	3	2
7												
8	19	18	17	16	15	14	13	12	11	10	9	8
9												
10	25	24	23	22	21	20	19	18	17	16	15	14
11												
12	31	30	29	28	27	26	25	24	23	22	21	20
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-13 GLO	LCRC L3, P42, Feb., 1976	LCRC L4, P89, Dec., 1990
Lucius Lyon, D.S. 1831	3/4" pipe	Capped rerod
Set post cor.	12" Walnut N 20 W 121.47'	Stop sign post N 60 E 45.6'
Secs. 32 & 33	Tel. cable marker N 65 W 32.46'	Spk. S side 14" Pine N 50 W 50.61'
Beech 19 N 7 W 13	St. sign N 70 W 26.36'	Spk. W side 14" Pine N 30 W 71.54'
Maple 12 N 79 E 28	PP W 136.6'	S leg of sign post N 85 W 24.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13 Found 1/2" rerod with cap in gravel road  
As per above wit. As per above wit.

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Approved by Allegan Co. Peer Group 5/14/96

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 5-14-96  
COUNTY REP. Paul J. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 Replaced 1/2" rerod with Allegan Co. Mon. 3/4" x 24" pin with cap	
Nail & Allegan Co. Remon Tag in SW side 18" Pine	N 45 W 50.24'
Nail & Allegan Co. Remon Tag in SW side 14" Pine	N 15 W 71.43'
Nail & Allegan Co. Remon Tag in SW cor. hse. #3615 @ brick	N 30 E 322.82'
Nail & Allegan Co. Remon Tag in N side PP	S 50 E 249.44'
C/L gravel road N-S, W 2'	
On C/L gravel road East, on pole line W	

Signed by John C. Bueche  
John C. Bueche, P.S. 13027  
Surveyor's Michigan License No. \_\_\_\_\_

Date 10-14-96

