

REMONUMENTATION

APR 07 1998

9-2

SECTION

Allegan County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>12W</u>	<u>F-1 (N1, 4)</u> <u>Dorr Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

98 JAN 21 PM 1:21  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.  
*Joseph A. Bueche*

FILED

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

I, John C. Bueche, in a field survey on April 2, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-1 GLO	LCRC L2, P310 Allegan Co.	LCRC 8603 Kent Co.
Not set	Fnd. wood stake & well point	1941 Leaded stone
	June, 1974 CP Co.	1981 LCRC 2307 fnd. 1/2" iron, set K.C. Mon.
	SW cor. HD. WI. S 15° E 24.11'	1986 LCRC 4427 reset Kent Co. Mon.
	30° Walnut N 70° W 68.94'	1988 LCRC 4652 Kent Co. Mon.
	L882, P226 Survey, 1976	1995 LCRC 8603 Kent Co. Mon.
	West 2653.95'; East 2649.07'	OVER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1 Found Kent Co. Mon. corner is common with S 1/4 33, 5-12 Section corners East & West are common as per GLO  
As per wit. in LCRC 8603

Meas. West 2652.56' (CP Co. 2653.95')  
Meas. East 2650.66' (CP Co. 2649.07')  
This position not established by original government surveyors.  
This monument is accepted as the best available evidence of the position of the corner.  
Peer group approved May 13, 1997.

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 5-13-97  
COUNTY REP. R.V.D.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1 Kent Co. Mon.  
Nail & Kent Co. Remon. Tag in N side PP S E 48.70'  
Nail & Kent Co. Remon. Tag in SW side 32° Ash N W 68.44'  
Nail & Allegan Co. Remon. Tag in W side 12° Ash N 16° E 63.01'  
Nail & Allegan Co. Remon. Tag in W side 8° Ash S 10° E 77.29'  
SE cor. conc. fnd. to hse. #2812 S 52° W 115.17'  
NE cor. conc. fnd. to hse. #2812 S 67° W 96.62'  
NW cor. conc. fnd. to hse. #2812 S 73° W 120.77'  
C/L gravel N-S, West 12'±



Signed by John C. Bueche, P.S. 13027 Date Sept 12, 1997  
Surveyor's Michigan License No. \_\_\_\_\_

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

0006 PAGE 067

Sheet 1 of 2

LCRC 8603

Std. Kent Co. Mon.

NE cor. hse. fnd. S 70° W 96.65'

Nail & Kent Co. Remon. Tag in SW side 30" Ash N 60° W 68.38'

Nail & Kent Co. Remon. Tag in NE side P&T pole S 54° E 48.59'

Nail & Kent Co. Remon. Tag in NW side 12" Ash N 18° E 63.02'

RECORDED IN THE OFFICE OF THE  
COUNTY CLERK OF KENT COUNTY  
MICHIGAN  
ON \_\_\_\_\_ 19\_\_\_\_  
AT \_\_\_\_\_