

COMMISSION

Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan
(County)

Located in:

Corner Code ##

- | | | |
|---------------------------------------|--------------------------|----------------------|
| 1. Public Land Survey | T <u>4N</u> R <u>12W</u> | <u>F-13 (S1, 33)</u> |
| | T _____ R _____ | <u>Dorr Twp.</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
James W. Clarke

97 JAN 22 PM 1:22

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John C. Bueche, in a field survey on October 1, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-13 GLO	LCRC L3, P25, Feb., 1976	5/8" rerod East 14.85'
Lucius Lyon, D.S.	1" iron	N 1/4 Sec. 4-3, 12
1831	E end 18" CMP	N 10 E 38.2'
Set qr. Sec. post	Tel. marker	N 25 E 32.37'
Beech 9 N 72 E 60	N end 18" CMP	N 40 E 27.8'
Beech 9 N 8 W 16	St. sign	S 40 W 20.4'
	S end 18" CMP	S 45 E 25.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13 Found 1" iron in bit. road
 As per above wit.
 And is accepted as a careful and faithful perpetuation of the position of the original corner.
 Approved by Allegan Co. Peer Group 5/14/96

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 5-14-96
 COUNTY REP. Rob T. ...

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 Replaced 1" iron with Allegan Co. Mon. 3/4" x 24" pin with cap
 Nail & Allegan Co. Remon. Tag in W side 24" Hickory N 5 W 288.62'
 Nail & Allegan Co. Remon. Tag in N side Twin Elm
 1-10"-14" (Nail in 10") S 70 E 98.57'
 Nail & Allegan Co. Remon. Tag in N side 8" Elm S 85 W 161.14'
 5/8" rerod East 14.85'
 Field division S, E 10'
 C/L bit. road S 1' Old tree line & fence North, W 33'
 C/L 2 track N, W 15'

Signed by John C. Bueche
 Surveyor's Michigan License No. 13027

Date 10-14-96

