

APR 07 1998

7-
7

Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Allegan (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>12W</u>	<u>G-1 (NE, 4)</u> <u>Dorr Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

98 JAN 21 PM 1:21
REGISTER OF DEEDS
ALLEGAN COUNTY
FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	10	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John C. Bueche, in a field survey on April 4, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-1 GLO	LCRC L1, P162 Allegan Co.	L895, P379
May, 1831	Dec., 1971	CP Co. Survey 1976
Lucius Lyon, DS	Mon. box 1.15' S of true cor.	Same as LCRC L1,
Intersected N.	SE cor. oil sta. ind. N 47°	P162
boundary & post	W 70.74'	Worksheet shows
B Ash 24 N 50	Nail C/L CP pole S 61° W 47.13'	West 2649.07'
E 12	Nail C/L MBT pole S 36° E 46.43'	East 2653.78' to
Ash 19 N 18 W 31	Nail C/L MBT pole N 40° E 42.13'	N 1/4 3
		No jog shown
		OVER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1 Found Kent Co. Mon. corner is common with SE 33 & SW 34, 5-12
As per wit. in LCRC 8616

Meas. West 2650.66' to N 1/4 4 (CP Co. 2649.07')
Meas. East 2646.69' to S 1/4 34, 5-12 (CP Co. 2653.78')
And is accepted as a careful and faithful perpetuation of the position of the original corner.
Peer group approved May 13, 1997.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 5-13-97
COUNTY REP. K.V.O.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1 Standard Kent Co. Mon. (4" Harrison in conc.)
Nail & Kent Co. Remon. Tag in SE side PP N 42° E 41.43'
Nail & Allegan Co. Remon. Tag in N side PP S 57° W 47.73'
NW cor. conc. ind. to garg. S 60° W 149.44'
SE cor. conc. ind. to hse. S 37° W 178.31'
NE cor. alum. sided garg. N 50° W 110.68'
SE cor. alum. sided garg. N 65° W 94.75'
On C/L bit. N-S, E-W



Signed by John C. Bueche Date Sept 12, 1997
Surveyor's Michigan License No. 13027

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1974
REVISED MAY 14, 1975
REVISED JAN., 1983

LCRC 8616 Kent Co.

Std. Kent Co. Mon.

Nail & Kent Co. Remon. Tag in SE side TP N 42° E 41.44'

Nail & Kent Co. Remon. Tag in NW side PP S 58° W 47.72'

NE cor. alum. sided garg. N 50° W 110.68'

SE cor. alum. sided garg. N 65° W 94.75'