

**Allegan County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Allegan  
(County)

Located In: Corner Code #

- |                                    |                          |                      |
|------------------------------------|--------------------------|----------------------|
| 1. Public Land Survey              | T <u>4N</u> R <u>12W</u> | <u>G-13 (SW, 34)</u> |
|                                    | T _____ R _____          | <u>Dorr Twp.</u>     |
|                                    | T _____ R _____          | _____                |
|                                    | T _____ R _____          | _____                |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____                |
|                                    | S _____ T _____ R _____  | _____                |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____                |
|                                    | S _____ T _____ R _____  | _____                |

97 JAN 22 PM 1:22  
REGISTERED  
ALLEGAN COUNTY  
REGISTER OF DEEDS STAMP & FILE NUMBER  
FILED

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	10	9	8	7	6	5	4	3	2	1		
7												
8	13	12	11	10	9	8	7	6	5	4	3	2
9												
10	16	15	14	13	12	11	10	9	8	7	6	5
11												
12	19	18	17	16	15	14	13	12	11	10	9	8
13												

I, John C. Bueche, in a field survey on October 1, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- |                |  |               |
|----------------|--|---------------|
| G-13 GLO       | LCRC L3, P25, Feb., 1976                     |               |
| Lucius Lyon,   | 3/4" iron                                    |               |
| D.S., 1831     | PK Nail in S side PP                         | N 45 W 42.28' |
| Set post cor.  | PK Nail in W side PP                         | N 30 E 79.96' |
| Sec's. 33-34   | PK Nail in TP                                | S 40 E 92.48' |
| Beech 7 N 47 E | 24" Hickory (face)                           | S 55 E 56.95' |
| 24             | SW cor. 3'x2' reddish gray rock              | S 40 W 40.45' |
| Beech 8 N 18 W | C/L bit. N-S, East 10' NW cor. sec. 3 (3-12) | East 33.00'   |
| 33             |  |               |

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- G-13 Found 3/4" iron in Mon. Box in bit rd.
- As per above wit.

And is accepted as a careful and faithful perpetuation of the position of the original corner  
Approved by Allegan Co. Peer Group 5/14/96

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 5-14-96  
COUNTY REP. John C. Bueche

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- |  |               |
|--|---------------|
| G-13 Replaced 3/4" iron in Mon. Box with 3/4" x 24" pin with cap |               |
| Nail & Allegan Co. Remon. Tag in SW side PP                      | N 45 W 42.50' |
| Nail & Allegan Co. Remon. Tag in W side PP                       | N 45 E 80.11' |
| Nail & Allegan Co. Remon. Tag in N side 18" Box Elder            | S 70 W 82.73' |
| Nail & Allegan Co. Remon. Tag in SW side 24" Oak                 | S 60 E 58.11' |
| On C/L bit rd. West, C/L gravel rd. E                            |               |
| On C/L bit rd. N extend South, C/L bit rd. N-S E 8.5'            |               |

Signed by John C. Bueche  
Surveyor's Michigan License No. 13027

Date 10-14-96

