

**Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
Allegan
(County)

Located in:	Corner Code #
T <u>4N</u> R <u>12W</u>	<u>H-13 (S1, 34)</u>
T _____ R _____	<u>Dorr Twp.</u>
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

97 JAN 22 PM 1:22
 REGISTER OF DEEDS
 ALLEGAN COUNTY
 FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	15	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John C. Bueche, in a field survey on October 1, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13 GLO No other information
 Lucius Lyon, D.S.
 1831
 Tamarack 6" for gr. sec.
 cor. tree

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 Nothing found at corner
 Distance from SW to SE of Sec. 34, 5305.72'. Set corner 1/2 way
 & on line between SW & SE cor. (2652.86' - 2652.86')
 About on C/L ditch North
 C/L gravel road E-W, South 1.5'

And is accepted as a careful and faithful reestablishment of the position of the original corner.

Approved by Allegan Co. Peer Group 5/14/96

APPROVED REMONUMENTATION CORNER
 P.A. 343 OF 1990
 ALLEGAN COUNTY


DATE APPROVED 5-14-96
 COUNTY REP. Paul A. Van Dine

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 Set Allegan Co. Mon. 3/4" x 24" pin with cap
 Nail & Allegan Co. Remon. Tag in E side PP N 10 W 68.62'
 "X" cut on top of CMP N 80 W 61.60' (E. Culvt.)
 "X" cut on top of CMP S 75 W 72.88' (E. Culvt.)
 SE cor. of small bldg. N 23 E 102.00'
 Allegan Co. Mon. East 16.50' N 1/4 sec. T3N, R12W
 Rerod West 19.41'
 C/L gravel road E-W, South 1.5'

Signed by John C. Bueche
 Surveyor's Michigan License No. 13027

Date 10-14-96



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS (YES) AUG 24, 1971
 I.A. No. 14, 1975
 REVISED JAN., 1983