

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

FILED

1/28/1999 2:44:39 PM

LIBER0006 PAGE361

For corners in

Allegan
 (County)

Located In: Dorr Twp. Corner Code # J-13

1. Public Land Survey

T 4 N R 12 W
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

JOYCE A. WATTS
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

I, Robert J Jonker, in a field survey on 10-29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. map-J.W. Hicks - no date
 40.00 set qr. sec. post nothing shown
 Beech 24 N37°E 17' 1983-per Tri County surveys-no info. of
 Beech 8 N35°W 35' value in their files-per Ray Moored

Jonker-1983-Land owner to N. owns land in SW $\frac{1}{4}$ & SE $\frac{1}{4}$ he showed me old pipe he put in N-S tree row before he removed the tree row. Set corner on line SW. & SE. Corners of section on line with pipe as described above.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Jonker capped $\frac{1}{2}$ " rerod
 replaced with 36" st. Allegan Co. Monument

And is accepted as the best available evidence of the position of the original corner.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED Nov. 10, 1998
 COUNTY REP. Robert J. Jonker

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

std. Allegan Co. Monument
 A/C tag - SW. side 17" Maple N10°W 40.74'
 Found pk.-W. side p. pole S48°W 95.56"
 Found nail-W. side tw. 10" Elm S31°E 33.27'
 SW. Corner brick hse. fnd. N37°E 88.84'
 J-1 Hopkins Twp., East 7.88'
 C/L E-W gravel road 2'S

Traverse J-13, I-13, 2643.83'
 Traverse J-13, K-13, 2661.99'

Signed by Robert J. Jonker
 Surveyor's Michigan License No. 21572

Date 11-9-98

