

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

LIBERO 006 PAGE 362

For corners in

<u>Allegan</u> (County)	Located In: Dorr Twp.	Corner Code # _____
1. Public Land Survey	T <u>4</u> N R <u>12</u> W	<u>K-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED
1/28/1999 2:44:39 PM
JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert J Jonker, in a field survey on 10-29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

J.W. Hicks-map-page #128
Co. Surveyor-calls for a
stone no
date

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. @ 80.00 ch., set post for sections 35 & 36
Beech 6 N43°E 5
Beech 6 N82°W 48

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found $\frac{1}{2}$ " rerod
Replaced with 36" std. Allegan Co. Monument

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED Nov. 10, 1998
COUNTY REP. [Signature]

And is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

36" std. Allegan Co. Monument
Found nail-N. side 18" Hickory N75°E 73.95'
C/L hole in top S. end 18" C.M.P. S75°W 59.00'
Set "cut mark" on N. end 18" C.M.P. N55°W 58.73'
Found pk. nail - SW. side fence Corner post S08°E 36.56'
K-1 of Hopkins Twp., West 33.14 feet
on line C/L of road to N., C/L of E-W Road is 2'N (both are gravel)
Traverse K-13, J-13, 2661.99'
Traverse K-13, L-13, 2650.98'



Signed by Robert J. Jonker
Surveyor's Michigan License No. 21572

Date 11-9-98