

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

LIBR0006 PAGE 363

For corners in

<u>Allegan</u> (County)	Located in:	Corner Code #
	Dorr Twp.	
1. Public Land Survey	T <u>4</u> N R <u>12</u> W	<u>L-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED  
1/28/1999 2:44:39 PM  
JOYCE A. WATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH  
  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert J Jonker, in a field survey on 10-29, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
G.L.O. Ratekin-1967  
S. side Sec. 36 point not set-used  
40.00 ch. set qr. post midpoint of mile  
Beech 15 N11 E 14  
Beech 13 N45 W 39

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED NOV. 10, 1998  
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Nothing found-set @ midpoint of mile, on line between SW. & SE. Sec. corners  
36" std. Allegan Co. monument, as per Ratekin sketch  
Fits the 1/8 line occupation to east & west

And is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
std. Allegan Co. Monument  
Found nail-E. NE. side 30" ash N50°W 37.76'  
A/C remon tag -SW. Side 14" maple N65°W 79.83'  
set pk. nail & tag-SE. side P. pole S85°W 180.70'  
set "X" cut-top N. side 40" conc. culv. S10°W 120.37'  
set pk. & tag-SW. side p. pole S74°E 175.24'  
C/L E-W road 1' +- N.



Traverse L-13, K-13, 2650.98'  
Traverse L-13, M-13, 2650.98'

Signed by Robert J. Jonker Date 11-9-98  
Surveyor's Michigan License No. 21572