

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

|                                       |   |                             |
|---------------------------------------|---|-----------------------------|
| <u>Allegan</u><br>(County)            | Located In:<br>Dorr Twp.                        | Corner Code #<br>M-5        |
| 1. Public Land Survey                 | T <u>4N</u> R <u>12W</u>                        | <u>                    </u> |
|                                       | T <u>      </u> R <u>      </u>                 | <u>                    </u> |
|                                       | T <u>      </u> R <u>      </u>                 | <u>                    </u> |
|                                       | T <u>      </u> R <u>      </u>                 | <u>                    </u> |
| 2. Property Controlling<br>in Section | S <u>      </u> T <u>      </u> R <u>      </u> | <u>                    </u> |
|                                       | S <u>      </u> T <u>      </u> R <u>      </u> | <u>                    </u> |
| 3. Miscellaneous<br>Property in Sec.  | S <u>      </u> T <u>      </u> R <u>      </u> | <u>                    </u> |
|                                       | S <u>      </u> T <u>      </u> R <u>      </u> | <u>                    </u> |

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

LIBR0006 PAGE368

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert J Jonker, in a field survey on 10-22, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |    |   |    |   |    |   |    |   |    |   |    |   |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. post  
Beech 7 S30W 19
- B. Ash 11 N66W 27

(see additional info. over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Ed 1/2" solid iron in Mon box  
by wit. listed (over)

And is accepted as a careful and faithful Perpetuation of the position of the original corner.

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED Nov. 24, 1998  
COUNTY REP. Rich D. Van Orden

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced iron with std. Allegan Co. monument.  
Found nail & tag - NE side guy pole N45°E 43.81'  
Found pk nail - SE side p. pole S35°W 44.59'  
SE Corner conc. block bldg N42°W 104.64'  
Allegan co. remon pin South 9.19' in mon box  
Set nail & tag - NE side p. pole S67°E 115.38'

Traverse M-5, M-4, 2645.38'

Signed by Robert J. Jonker  
Surveyor's Michigan License No. 21572

Date 11-9-98



M-5

M-S DORR TWP.

1. 1973, Ratekin - LCRC #2-161 10-22-98  
 Part "B" - fd. 1/2" iron pin  
 Part "C" - took Wit.  
 NW Corner block bldr. S45°E 62.44' out  
 P. pole S35°W 43.93' check ok  
 16" maple N35°E 70.20' out
  
2. 1974, M.V.K. LCRC #2-354  
 Part "B" - fd. 1/2" solid iron (checks previous wit.)  
 Part "C" - took wit.  
 Nail - guy pole NE 43.81' check ok  
 Nail - guy p. pole SW 44.59' check ok  
 NW cor. conc. bl. bldg. SE 62.57' out  
 1" solid iron S. 9.17' check ok  
 SE Cor. Conc. bl. bldg. NW 104.64' check ok  
 18" maple NNE 70.4' check ok
  
3. Rec. survey - 1973, Ratekin - L. 841, P. 540 iron  
 NW Cor. bldg. S45°E 62.44' out  
 P. pole S35°W 43.93' check ok  
 16" Maple N35°E 70.20' check ok
  
4. 1980, rec. survey, M.V.K. - 1/2" solid iron, L. 992, P. 757, 758, 759  
 Nail p. pole SW 44.59' check ok  
 18" maple NNE 70.4' check ok

LIBR0006 PAGE369