

RF

MAR 07 2000

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Allegan  
(County)

Located In:  
Common corner

Corner Code #

- 1. Public Land Survey
 

T	R	
T4N	R11W	A-9 Leighton
T4N	R12W	M-9 Dorr ✓
T	R	
- 2. Property Controlling in Section
 

S	T	
S	T	
- 3. Miscellaneous Property in Sec.
 

S	T	
S	T	

REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.

00 FEB - 1 AM 8:42

FILED

LIBRARY / PAGES 50

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Robert J Jonker, in a field survey on 12-8, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO survey - East Boundary - M-9  
North - E. side 25  
80.0 ch. set post se 24 and 25  
R. oak 9 N42°W 43'  
W. oak 15 S5°W 14'

GLO survey A-9 W. between 19 & 30  
76.64 ch. Intersect W. boundary  
at post ( no wit. noted on  
page 137)

over

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

Found 1" steel pin with rerod rusted to one side of it  
Removed & replaced with std. 3/4" X 36" std. monument

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group approved 12-14-99

Road traverse M-9-M-10 2643.20'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 36" std. Allegan Co. Monument  
PK nail on top of guard post S13°E 19.66'  
PK nail on top of guard post N43°W 29.57'  
PK nail on top of guard post N66°W 62.76'  
PK nail on top of guard post N42°E 24.88'  
Spike on top guard post S50°W 26.68'

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED DEC. 14 1999  
COUNTY REP. [Signature]



Signed by Robert J. Jonker  
Surveyor's Michigan License No. 21572

Date 12-10-99

M-9 Part "A" continued

1. Oct. 1869 - Survey by E. Strong DS  
NE Cor. Sec. 25 - 14 X 11 X 7 - stone
2. old maps  
1/2 mile to N - 40.1 ch.  
1/2 mile to S - 40.09 Ch.
3. 1956 MDOT - 1" iron  
CP NW 42.8'  
G. pole NE 57.4'  
CP pole SE 60.5'  
Steel fe. post SW 34.3'  
18" oak NE 45.1'
4. MDOT map 1956  
Shows corner as common with T4N, R11W  
1/2 to North - 2664.12'  
1/2 to South - 2652.54'
5. SW Cor. Sec. 19 - Leighton  
Ratekin - 1978 Not noted what was found  
Guard rail post SW 26.73'  
Guard rail post SSE 19.74'  
Guard rail post NE 24.87'  
Guard rail post NW 29.52'
6. Recorded surveys by MVK  
Liber 992, Page 750 and Liber 849, Page 445  
Same as LCRC #L-3, Page 294
7. MVK 1979, LCRC #L-3, Page 294  
Part B Fd. 1" solid rod on C/L gravel  
Part C  
Nail in guard post SSE 20.05'  
Nail in guard post NE 25.31'  
Nail in guard post WNW 62.00'
8. Holland Eng.  
Part B Rd. 1" solid Rod on C/L gravel  
Part C  
Nail in guard post SSE 20.05'  
Nail in guard post NE 25.31'  
Nail in guard post WNW 62.00'
9. Recorded survey, Jonker, 1984  
1" steel pin  
PK Nail top guard post S13°E 19.66'  
PK nail top guard post N43°W 29.57'  
spk. top guard post S50°W 26.68'  
PK nail top guard post N66°W 62.76'  
PK nail top guard post N42°E 24.88'
10. Wightman Moored 1994  
used corner - no witnesses

MARNEY &  
R.F. ...

MAR 07 2000

SECTION

Out  
Out  
Out  
Out  
Out

Check OK  
Check OK  
Check OK  
Check OK  
Check OK

Check OK  
Check OK  
Check OK

Check OK  
Check OK  
Check OK

Check OK  
Check OK  
Check OK  
Check OK  
Check OK

- 
- |  |   |
|--|---|
| <p>A-9</p> <ol style="list-style-type: none"> <li>1. Old wit. map - calls for stone &amp; gov. wit.</li> <li>2. LCRC # 3-103, MVK 1976<br/>Part B - fd. 1" iron<br/>Part C -<br/>Nail on top guard rail post SW 26.73'<br/>Nail on top guard rail post SSE 19.74'</li> </ol> | <ol style="list-style-type: none"> <li>3. Recorded survey, MVK L.899, P. 85<br/>Same as LCRC 1976</li> <li>4. Recorded survey by MVK 1976<br/>same wit. as LCRC</li> <li>5. Survey by Ragekin 1978<br/>Stone &amp; gov. wit.</li> </ol> |
|--|---|

LIBRARY / 10000000