

**SURVEY
REMONUMENTATION**

APR 29 1999

SECTION

Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|---------------------------------------|--------------------------|---------------|
| <u>Allegan</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>4N</u> R <u>13W</u> | A-3 (NW, 7) |
| | T ___ R ___ | Salem Twp. |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

LIBR0007 PAGE 55

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John C. Bueche, in a field survey on May 8, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:
 A-3 GLO, 1831 LCRC 3-252, July, 1979, Greer
 Lucius Lyon, DS Fnd. Mon. Box
 To West boundary "T" iron Overisel Cor.
 48 S. of post N 30.26'
 Beech 6 N 29 E 38 TP S 50° W 34.60'
 Beech 6 S 31½ E 14 St. sign N 35° E 43.78'
 PP N 25° W 146.86'
 NW cor. conc. post 69.31'

Surveys
1015-717 HEI April, 1981
1143-60 HEI March, 1986

Same as left

OVER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY

A-3 Found 2" pipe in Mon. Box on Township Line between (M-3 & M-4, 4-14)
 Overisel Cor. N 30.26'
 TP S 50° W 34.60' cut off
 PP N 25° W 146.86'
 NW cor. conc. post 69.31'

DATE APPROVED JUNE 9, 1998
COUNTY REP. [Signature]

Peer group approved

Traverse 2658.67'

And is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3 Placed 3/4" x 24" Pin with Allegan Co. Cap inside 2" pipe in Mon. Box
 Nail & Allegan Co. Remon. Tag in NE side PP S 35° E 61.85'
 Nail & Allegan Co. Remon. Tag in top of cut off pole S 65° W 34.79'
 Nail & Allegan Co. Remon. Tag in S side 18" Walnut N 65° W 133.36'
 Nail & Allegan Co. Remon. Tag in E side PP N 15° W 147.40'
 C/L of conc. ROW marker N 40° W 69.17'
 Allegan Co. Mon. in Mon. Box M-3 (SE 1, 4-14) North 30.24'
 C/L E-W bit. North 12±; on C/L bit. East extended West
 On C/L of gravel road N-S



Signed by John C. Bueche
 Surveyor's Michigan License No. 13027

Date 6-4-98

SURVEY
REMONUMENTATION

APR 29 1990

SECTION
A-3 SALEM TWP.
PART A - continued

HEI inform. sheet
Fnd. MB 12' S of C/L WRB 72
Pipeline S 850'
Pipeline E 408'
Stone 15' S of C/L
20" Maple SE 140.80'
26" Maple W 95.70'
12" Hickory NW 148.00'
Stone 33' N

1929 stone
2824.3' to N ¼
16" Maple SE 74.9'
24" Maple SE 73.3'
18" Maple SE 58.3'

LIBERO 007 PAGE 56

