

**SURVEY
REMONUMENTATION**

APR 29 1999

SECTION

**Alleghan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Alleghan</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T4N R13W	A-6 (W $\frac{1}{2}$, 18)
	T___ R___	Salem Twp.
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

FILED
1/28/1999 2:44:39 PM
JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

LITER 007 PAGE 61

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John C. Bueche, in a field survey on May 7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-6 GLO Did not set corner	Survey HEI, Sept., 1977 L919-722 Fnd. steel bar 24" Oak NNW 144.20' PP ESE 30.03'	LCRC 3-408. Jan., 1985, Jonker Nail S side PP S 75° E 30.02' Nail NW side PP S 55° W 64.05' Nail NE side 5" Tw. Oak N 70° W 64.45' Nail E side 8" Oak clump N 15° W 112.70'
	Alleghan notes 12" Oak NW 88.5' 12" Oak NNW 143.8'	

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED JUNE 9, 1998
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


A-6 Found 3/4" steel bar on Township Line between M-6 & M-5, 4-14, in gravel road
PP ESE 30.03'
Nail S side PP S 75° E 30.02'
Nail NW side PP S 55° W 64.05'

Traverse 2638.67'
Peer group approved

This position not established by original government surveyors.
This monument is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6 Replaced steel rod with 3/4" x 24" Pin with Alleghan Co. Cap in gravel road
Nail & Alleghan Co. Remon. Tag in S side PP S 25° E 29.85'
Nail & Alleghan Co. Remon. Tag in N side 12" Poplar N 35° W 49.73'
Nail & Alleghan Co. Remon. Tag in N side 10" Oak N 85° W 45.22'
Nail & Alleghan Co. Remon. Tag in N side PP S 60° W 64.14'
Nail & Alleghan Co. Remon. Tag in E side 12" Oak S 25° W 82.87'
Alleghan Co. Mon. M-6 (E 1/4 13, 4-14) South 16.74'
North edge woods North 139'±
On C/L gravel road N-S; C/L dr. West, South 17'±



Signed by John C Bueche
Surveyor's Michigan License No. 13027

Date 6-4-98

SURVEY
REMONUMENTATION

APR 29 1999

SECTION

A-6
SALEM TWP.

LIBRO 007 PAGE 62

