

**SURVEY  
REMONUMENTATION**

APR 29 1999

**SECTION**

**Allegan County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Allegan (County)	Located In:	Corner Code #
1. Public Land Survey	T 4N R13W	A-7 (SW, 18)
	T R	Salem Twp.
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH

LIBR0007 PAGE 63

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John C. Bueche, in a field survey on May 7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-7 GLO, 1831	HEI inform. sheet	LCRC 3-408, March, 1985
Lucius Lyon, DS	Fnd. iron in Mon. Box	Jonker, Recorded Jan., 1986
To West boundary	JPC 1977	Fnd. 1" steel pin in Mon. Box 1.42' East of
50 North	SE cor. Sec. 13 S 33.31'	West line Sec. 18
B. Ash 4 S 29	PP ESE 175.70'	Nail NE side TP S 25° E 77.14'
E 5		1" steel pin South 33.4'
W. Ash 7 N 70		"X" cut in N. end conc. culvt. N 65° W 40.85'
E 34		Inter. Sec. lines West 1.42'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7 Found 1" steel pin in Mon. Box 1.42' East of Township Line between (M-7 & M-6, 4-14)  
PP ESE 175.70'±  
1.42' E. of Twp. Line.  
1" steel pin South 33.4'

Peer group approved JUNE 9, 1998  
Traverse 2638.50'

And is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7 Placed 3/4" x 24" Pin with Allegan Co. Cap on Township Line  
Nail & Allegan Co. Remon. Tag in E side 22" Elm S 20° W 118.46'  
Nail & Allegan Co. Remon. Tag in S side PP S 90° W 152.61'  
Nail & Allegan Co. Remon. Tag in N side PP S 75° E 177.02'  
NW cor. metal bldg. S 35° W 138.80'  
SE cor. metal bldg. N 30° W 183.80'  
Allegan Co. Mon. M-7 (SE 13, 4-14) South 33.40'  
Steel pin in Mon. Box East 1.42'  
C/L bit. E-W South 20'±; C/L gravel road North is East 6'±

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY

DATE APPROVED JUNE 9, 1998  
COUNTY REP. [Signature]



Signed by John C. Bueche  
Surveyor's Michigan License No. 13027

Date 6-4-98

SURVEY  
REMONUMENTATION

APR 20 1988

A-7 SALEM TWP.  
PART A - continued

SECTION

LCRC 3-399, June, 1985, Rosema  
Recorded June, 1985  
3/4" iron in Mon. Box  
PK in W side post Tel box NW 50.80'

HEI inform. no date  
PK E side PP SSW 69.08'  
PK SW side PP SSE 77.47'  
C/L pav't. S 19'  
SE cor. 13, 4-14 South 33.36'

LDERO007 PAGE064

