

Allegan County Remonumentation  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

MAR 1 1993  
 COV...

For corners in  
Allegan  
 (County)

Located In:

Corner Code #

1. Public Land Survey	T <u>4N</u> R <u>13W</u>	<u>B-13 (S 1/4, 31)</u>
	T _____ R _____	<u>Salem Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1993 DEC 17 PM 1:56  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY, MICHIGAN  
 [Signature]

FILED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, John C. Bueche, in a field survey on October 26, 19 93  
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-13 1 1/4" solid iron 1968	Axle shaft K.V.O. 1987	1" steel pin
18" Hickory NNW 20.5'	20" Hickory N 39.23'	LCRC L04, P91 3-8-85
18" Hickory N 38.4'	4" Hickory SW 59.73'	Capped iron N 33'
2472.04' W to SW 31	Twp. cor. W 33.0'	#23520 Kirk V.O.
2645.20' E to S 1/4 31		On E-W gravel, tree line North

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13 Found 1 1/4" x 30" solid rod down 10"  
 18" Hickory N 38.4' 20" Hickory N 39.23'  
 4" Hickory SW 59.73'  
 Meas. W to SW 31, 2472.74'  
 Meas. W to N 1/4 6, 3-13, 33.00' on line between S 1/4 & SW 31, 3-13


And is accepted as a careful and faithful perpetuation of the position of the original corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13 Replaced 1 1/4" solid rod with Std. Allegan Co. Mon. (3/4" x 24" rod & cap)  
 Conc. Nail & Allegan Co. Remon. Tag in W side 20" Hickory N 0° E 39.23'  
 Conc. Nail & Allegan Co. Remon. Tag in W side 12" Elm S 50° E 47.53'  
 Conc. Nail & Allegan Co. Remon. Tag in E side 10" Maple S 30° W 59.54'  
 Conc. Nail & Allegan Co. Remon. Tag in N side TP S 80° W 243.84' EDM  
 Allegan Co. Mon. & Cap W 33.00' (N 1/4 6, 3-13)  
 Tree line S is E 2'±  
 C/L E-W gravel road is N 2'±  
 C/L two track N is W 15'±  
 Meas. by hand

Signed by John C. Bueche  
 Surveyor's Michigan License No. 13027

Date Oct 26 1993



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983