

COMMISSION

For corners in

**Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

Allegan (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>13W</u>	<u>C-13 (SW, 32)</u> <u>Salem Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

0393 DEC 17 PM 1:56
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
 J. C. BUECHE

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, John C. Bueche, in a field survey on October 26, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-13 Angle iron, no date	Angle iron, LCRC L2, P93, 5-8-73	1 1/2" angle iron, 10-31-91
St. sign SSW 23.83'	SW 70.85' TP	15" Cedar SE 59.85'
NE cor. hse. fnd. ESE 85.28'	SW 24.00' st. sign NE 49.82' TP	TP NE 49.40'
NW cor. hse. fnd. SE 74.1'	NW 87.95 Tw. Cherry 2645.20' W to S 1/4 31	C/L st. sign SSW 41.32'
Gas vent NE 42.23'	2649.39' E to S 1/4 32	TP SW 70.83'
SE cor. old sch. hse. NW 138.97'	33' W to NE 6, 3-13	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13 Found angle iron 36" long down 10"	SW 70.85' TP	Nail & Tag 15" Cedar SE 59.85'
Gas vent NE 42.23'	NE 49.82' TP	Nail & Tag TP NE 49.40'
Meas. W to S 1/4 31, 2645.06'		Nail TP SW 70.83'
Meas. W to NE 6, 3-13, 33.00' on line between SE & S 1/4 31, 4-13		


And is accepted as a careful and faithful perpetuation of the position of the original corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13 Replaced angle iron with Std. Allegan Co. Mon. (3/4" x 24" Pin & Cap)
 Conc. Nail & Allegan Co. Remon. Tag in N side 16" Cedar S 45° E 59.90'
 Conc. Nail & Allegan Co. Remon. Tag in E side 18" Ch. Elm S 10° W 74.77'
 Conc. Nail & Allegan Co. Remon. Tag in E side TP S 65° W 70.77'
 Conc. Nail & Allegan Co. Remon. Tag in S side 6" x 8" fence cor.
 N 55° E 45.37'
 C/L of E-W gravel road N 3'±
 C/L of gravel road N, W 9'±
 C/L of gravel road S, W 29'±
 Meas. by hand

Signed by John C. Bueche
 Surveyor's Michigan License No. 13027

Date Oct 26, 1993



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983