

**SURVEY
REMONUMENTATION**

APR 29 1998

SECTION

Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Allegan</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4</u> N R <u>13</u> W	F-13 (S $\frac{1}{4}$, 33)
	T ___ R ___	Salem Twp.
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

FILED
1/28/1999 2:44:39 PM
JOYCE A. MATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

19980007 MHD 71

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John C. Bueche, in a field survey on April 13, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-13 GLO, 1831	LCRC 2-36, Sept., 1972	LCRC 4-387, Aug., 1994 Erickson
Lucius Lyon, DS	Ratekin	Found 3/4" iron
Set 1/4 sec. post	Found 3/4" iron	N 79° W 125.00' N&T S. side
Maple 16" bears N 68 E 35	7' N. of road C/L	Quad. 16" Oak
Maple 6" bears N 86 W 23	10" & 6" Tw. Oak	S 42° W 67.20' N&T 29245
Old notes stake & stone	S 45 W 67.0'	NW Tw. 16" & 12" Oak
Oak 6" NW 88.4'	TP N 80 W 87.29'	N 86° E 132.66' N&T 29245
Oak 6" SW 67.0'		S. side Tw. 16" Oak 4.5' high
		S 56° E 71.07' N&T 29245

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
N. 8" Catalpa 2.5' high

F-13 Found 3/4" iron in gravel road; no field division North

As per above wit.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED MAY 12, 1998
COUNTY REP. John C. Bueche

And is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 Replaced 3/4" iron with 3/4" x 24" Pin with Allegan Co. Cap in gravel road
Nail & Allegan Co. Remon. Tag in N side 8" Sass S 40° E 71.14'
Nail & Allegan Co. Remon. Tag in E side 8" Sass S 65° E 54.20'
Nail & Allegan Co. Remon. Tag in W side 14" Elm S 35° W 34.02'
Nail & Allegan Co. Remon. Tag in SW side 10" Sass N 50° W 48.82'
Nail & Allegan Co. Remon. Tag in W side 6" Sass N 20° E 37.78'
Allegan Co. Mon. F-1 (N 1/4 4, 3-13) West 60.50'
C/L gravel road E-W is South 6'±



Signed by John C. Bueche
Surveyor's Michigan License No. 13027

Date 5-8-98