

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Allegan
 (County)

Located In: Corner Code #

1. Public Land Survey	T <u>4N</u> R <u>13W</u>	G-6
	T ___ R ___	E 1/4 Cor.
	T ___ R ___	Sec. 16
	T ___ R ___	W 1/4 Cor.
2. Property Controlling in Section	S ___ T ___ R ___	Sec. 15
	S ___ T ___ R ___	Salem Twp.
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	
	S ___ T ___ R ___	

1993 DEC 30 PM 2:43
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
Joyce A. Latta

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kirk VanOrder, in a field survey on December 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-6
 •GLO set post @ 40.00 chains North of G-7.
 7" Beech N31°E 11 links
 7" Beech S71°W 35 links
 •Burnips Corners Plat 12-1-1899, E.P. Waterman, stone
 •MacDougall notes - Fd. stone
 SW cor. house NE 50.81'
 NE cor. store SW 54'
- SE cor. garage NW 36.7'
 •LCRC (L.1, P.342) 4-11-1972
 1 1/2" iron in monument box
 C/L Manhole S 20.0'
 SW cor. C.B. frame N60°E 34.45'
 NW cor. C.B. frame S60°E 34.95'
 •K.V.O. survey 3-15-1990 #90-2152
 Set capped 1/2" rerod
 C/L mon. box NW 7.35'
 SW cor. house NE 49.92'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-6
 Found 1 1/2" iron in monument box. Determined to be improperly established and was discounted.
 Found 1/2" capped rerod. Rod agrees with plat of Burnips Corners (L.2, P.44) done by E.P. Waterman Dec. 1, 1899. Corner sits at the middle of the R.O.W. of intersection of Main St. & North St.

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-6
 Replaced 1/2" capped iron with standard Allegan Co. monument (3/4" x 24" steel rod with red plastic cap).
 SW corner house with aluminum siding AZ. 55°26'± 49.93'
 NE corner stone foundation AZ. 125°35'± 104.81'
 NE corner concrete porch AZ. 224°53'± 46.69'
 SE corner concrete block foundation AZ. 296°15'± 146.91'

Signed by *[Signature]*
 Surveyor's Michigan License No. 23520



Date 12-30-93

LIBER 001 PAGE 321