

MAR 10 1994

Allegan County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
**Allegan County**  
(County)

	Located In:	Corner Code #
	Salem Twp.	
1. Public Land Survey	T <u>4N</u> R <u>13W</u>	<u>I-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1993 DEC 30 PM 2:4

FILED

Register of Deeds Stamp & File Number

REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.

I, Robert Jonker, in a field survey on December 14, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21	22	23	24			
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original G.L.O. survey - set post	LCRC rec. in L. 3, P. 86
8" Beech S 57° W 16 links	Iron, 1976, old wit.
8" Beech S 78° E 8 links	Fence post N 31.7'
	P. pole SE 137.2'
Took new wit.: 1976	St. sign N 25.2'
	3" W. Cherry SW 36.7'
Pk P. pole SE 77.02'	
PK fence post SE 61.15'	
PK Tri. 8" W. Cherry S 36.32'	PK Quad. 5" Maple N 35.10'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/8" Rod in Mon Box per 1976 wit.

P. pole SE 77.02'	Per 1985 wit.
St. sign N 25.2'	14" Pine NE 78.2'
Quad, Maple N 35.1'	Capped iron N 33'
	P. pole SE 77.08'


Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced rod with 3/4"x24" standard capped Allegan Co. Monument.

Set N & T E. wide Penta Maple	Az. 20°, 35.89'
Fd. PK N. side P. pole	Az. 218°, 64.32'
Fd. PK W. side P. pole	Az. 139°, 77.10'
Fd. Nail S. side 14" Pine	Az. 75°, 89.40'

on C/L E-W, S, and fence line to North



Signed by Robert J. Jonker Date 12-22-93  
 Surveyor's Michigan License No. 21572

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983

Part A - continued I-11

Old County Surveyors records - No date, calls for a stone; 1897 calls for a Pine Stake

		later Co. Surveyors records:	
2" Pipe			1 3/4" Iron Pipe
P. pole	SE 137.2'		Triple 12" W. Cherry SW 36.39'
Fence post	N 31.7'		Corner fence post N 31.7'
St. sign	N 25.2'		Center of St. sign post N NE 23.48'
3-8" W. Cherry	SW 36.7'		Tel. junction box NE 100.97'
			P. pole SE 137.87'

(rec. by Douglas W. Bonnema, L. 1, P. 158)

Survey recorded by Jonker Land Survey, 1985

PK SW side P. pole	SE 77.08'
Nail NW side 14" Pine	NE 78.2'
Capped Iron	N 33'

Kirk VanOrder, 1980

3/8" Steel Rod in Mon Box	
PK P. pole	SE 77.11'
PK P. pole	SW 64.30'
12" Penta Maple	NE 35.90'
14" Pine	NE 89.88'