

# SURVEY REMONUMENTATION

APR 29 1999

## ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

### SECTION

For corners in

Allegan			
(County)	Located In:	Corner Code #	
	Salem Twp.		
1. Public Land Survey	T <u>4</u> N R <u>13</u> W	J-5	
	T <u>    </u> R <u>    </u>		
	T <u>    </u> R <u>    </u>		
	T <u>    </u> R <u>    </u>		
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>		
	S <u>    </u> T <u>    </u> R <u>    </u>		
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>		
	S <u>    </u> T <u>    </u> R <u>    </u>		

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

FILED 1/28/1999

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Robert J Jonker, in a field survey on 10-6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5										●			
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 G.L.O. Jonker-1983, checked with Tri Co. Surveys, No info  
 39.8 ch. Set qr. sec. post Jonker-1983, set at midpoint of mile, on S. line  
 Beech 15 N60W 15 lks of Section.  
 Beech 14 S79E 15 lks Took wit. - Jonker capped iron  
 PK-W. side p. pole S05°W 35.45'; on C/L gravel to N.  
 NW. Corner garage fnd. S30°W 87.36; on tree line  
 to the South.  
 C/L W. end C.M.P. N40°W 36.0'; C/L E-W. part. is 1'  
 North.  
 C/L E. end C.M.P. N45°E 33.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found Jonker capped rered in Mon box per wit. listed in "A" above.  
 And is accepted as a careful and faithful reestablishment of the position of the original corner.

APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED NOV. 10, 1998  
 COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Replaced with 36" std. Allegan Co. capped monument  
 P.K. nail in West side P. pole S07°W 35.54'  
 NE. Corner garage fnd. S32°W 87.45'  
 AC tag in NE. side fc. post N25°W 47.69'  
 capped iron N50°E 46.23'  
 C/L of 144th Ave. N. 1'  
 C/L of 27th St. W. 3'



Signed by Robert J. Jonker  
 Surveyor's Michigan License No. 21572

Date 10-9-98