

Allegan County Remonumentation
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
COMMISSION
Allegan Co.
 (County)

Located in: Salem Corner Code #
 Twp. _____

1. Public Land Survey T _____ R _____
 T 4N R 13W J-11
 T _____ R _____
 T _____ R _____
2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1993 DEC 30 PM 2:43
Robert J. Jonker
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
 Register of Deeds Stamp & File Number

FILED

I, Robert Jonker, in a field survey on December 14, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original GLO wit., set stake
 Beech, 10" S 0° E 25 links
 Maple, 12" N 75° E 21 links


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2"x2' 4 1/2" rorod per Nederveld wit. of 1978 & Jonker wit. of 1984.

Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced with 3/4"x36" standard capped Allegan Co. Monument
 Set PK & T SE side new p. pole Az. 224°, 59.94'
 Set N & T NE side 32" W. Cherry Az. 299°, 60.90'
 Set N & T W. side 14" Pine Az. 23°, 41.52'
 NW corner brick house #2696 Az. 162°, 84.03'
 C/L E-W gravel road is 2'± North; on old fence & occupation line to the North
 Split rail fence to South is 3'± West



Signed by Robert J. Jonker Date 12-22-93
 Robert J. Jonker
 Surveyor's Michigan License No. 21572

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

Over for Sheet 2

LIBER 004 PAGE 312

Part "A" continued J-11

Old County Surveyors notes of 1896 & 1897 call for a stake

Later County surveyors notes call for a 3/8" iron set over stone

Old County Surveyors notes found remains of old stake in hole

Set 1/2" iron
 Iron fence post N 22.4'
 26" Cherry NW 59.9'
 P. pole SW 61.45'

12" Oak NE 46.93'
 8" Sas. NW 46.09'
 10" Dbl. W. Cherry SW 41.58'
 10" Oak SE 55.69'
 5/8" solid rod W 23.15'
 (recorded by Doug Bonnema in L. 1, P. 159)

Jonker Land Surveys, 1984, recorded survey

1978, Nederveld & Associates, round iron

P. pole SW Nail in face 61.3'
 C/L steel fence corner post N 22.45'
 30" Cherry WNW 59.86 Nail in face