

**SURVEY  
REMONUMENTATION**

APR 29 1998

**SECTION**

Alleghan County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Alleghan</u> (County)	Located In:	Corner Code #/
1. Public Land Survey	T <u>4N</u> R <u>13W</u>	<u>J-13 (S<math>\frac{1}{4}</math>, 35)</u>
	T _____ R _____	<u>Salem Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED  
1/28/1999 2:44:39 PM  
JOYCE A. WATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH

**Register of Deeds Stamp & File Number**

LIBERO007 HABU 16

I, John C. Bueche, in a field survey on April 10, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

J-13 GLO, 1831 Lucius Lyon, DS Beech 6" for quarter sec. cor.	LCRC 1-159, Nov., 1971 Bonnema Found stone "X" on top Set 3/8" iron pipe over stone 12" Oak NE 46.93' 8" Sass. NW 46.07' 10" Dbl. W. Cherry SW 41.58' 10" Oak SE 55.69' 5/8" solid rod W 23.15'	LCRC 1-285, May, 1972 Ratekin Found 1/2" pipe 12" Oak NE 46.93' 8" Sass. NW 46.07' Dbl. 10" W. Cherry SW 41.58'
--	---	---

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

J-13 Found 1/2" rerod on C/L old county road E-W; on East edge of bit. road, Windingway in Sandy Pines Resort  
10" Oak SE 55.69'±  
"T" iron W 23.15'±

8" Sass. NW 46.07'± stump

And is accepted as a careful and faithful perpetuation of the position of the original corner.

**APPROVED REMONUMENTATION CORNER**  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED MAY 12, 1998  
COUNTY REP. [Signature]

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

J-13 Replaced 1/2" rerod with 3/4" x 36" Pin with Alleghan Co. Cap  
Nail & Alleghan Co. Remon. Tag in N side 14" W. Cherry S 70° W 62.19'  
Nail & Alleghan Co. Remon. Tag in E side 10" Maple S 3° W 75.37'  
Nail & Alleghan Co. Remon. Tag in NE side 18" Oak S 45° W 55.87'  
Nail & Alleghan Co. Remon. Tag in W side 10" Sass. N 65° W 55.91'  
Nail & Alleghan Co. Remon. Tag in N side 10" Pine N 26° E 42.52'  
On C/L old county road E-W; on East edge bit. road NW, SE  
Alleghan Co. Mon. J-1 (S 1/4 35, 4-13) East 23.15'



Signed by John C. Bueche Date 5-8-98  
Surveyor's Michigan License No. 13027