

REMONUMENTATION

APR 25 1995

Allegan County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION  
For corners in

<u>Allegan</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>13W</u>	<u>K-1(NE, 2)</u>
	T ___ R ___	<u>Salem Twp.</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1994 DEC 16 AM 9:55  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY, MICH.  
 J. A. ...  
 FILED  
 Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21	22	23	24			
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John C. Bueche, in a field survey on September 29, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-1 Set post	K-1 LCRC-L3 P185, Apr., 1978	K-13 Sec. 35, 3-13 T.K.A.
Beech 6" N 15°	1" solid iron	No date
W 28 lks	Nail in SW side PP	1" pipe, boat spk. @ surface
Beech 7" N 62°	N 55° W 77.95'	SW cor. conc. blk. bldg.
E 49 lks	SE cor. conc. hdwl.	S 40° E 83.75'
Jan., 1832	N 20° W 35.22'	Road sign N 45° E 56.2'
L. Lyon, D.S.	NE cor. conc. hdwl.	TP N 45° W 60.67'
	S 30° E 35.10'	
	NE'ly cor. hse. fnd. S 65° W 145.65'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


K-1 Found 1" x 24" solid iron  
 Nail in SW side PP  
 N 55° W 77.95'  
 SE cor. conc. hdwl.  
 N 20° W 35.22'  
 NE'ly cor. hse. fnd. S 65° W 145.65'

And is accepted as a careful and faithful perpetuation of the position of the original corner

APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 10-11-94  
 COUNTY REP. John C. Bueche

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1 Replaced 1" solid iron with 3/4" x 24" pin with Allegan Co. Remon. Cap  
 Nail & Allegan Co. Remon. Tag in W side PP S 30° W 163.49'  
 Nail & Allegan Co. Remon. Tag in SW side PP N 45° W 78.05'  
 NE'ly cor. hse. fnd. S 65° W 145.58'  
 SE cor. conc. hdwl. N 10° W 35.22'  
 C/L gravel N-S E 4'±  
 C/L gravel E-W N 2'±



Signed by John C. Bueche  
 Surveyor's Michigan license No. 13027

Date Oct 10, 1994

LIBER 0005 PAGE 034