

SURVEY & REMONUMENTATION

APR 25 1995

Allegan County Remonumentation LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

Allegan (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>13W</u>	<u>K-2(E1, 2)</u>
	T _____ R _____	<u>Salem Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

1994 DEC 16 AM 9:55
 Register of Deeds Stamp & File Number
 Joseph A. Bueche
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN

FILED

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21							
7													
8	16	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John C. Bueche, in a field survey on September 29, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-2 Set post Beech 7"	K-2 LCRC-L2, P360, Jan., 1975 CP Co. Set rebar prorated Gov't.	
S 60° W 8 lks	Dist. on Sec. line	
Beech 6"	PP S 20° E 86.67'	T.K.A. 1976
N 81° E 17 lks	8' E of C/L	Same as LCRC-L2, P360
Jan., 1832	4.5' N of fence E	Holland Eng.
L. Lyon, D.S.		Same as LCRC-L2, P360

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-2 Found 1/2" reroed

PP S 20° E 86.67'
 8' E of C/L
 Did not see fence E

And is accepted as a careful and faithful perpetuation of the position of the original corner


APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 10-11-94
 COUNTY REP. John C. Bueche

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2 Replaced 1/2" reroed with Allegan Co. Remon. (3/4" x 24" pin with Cap)
 Nail & Allegan Co. Remon. Tag in NW side 16" Hickory N 40° E 48.47'
 Nail & Allegan Co. Remon. Tag in N side 10"-14" Hickory N 90° E 29.95'
 Nail & Allegan Co. Remon. Tag in S side 10" Pear S 70° E 26.98'
 Nail & CP Cap in W side PP S 20° E 86.67'
 C/L gravel Rd. N-S E 8'±
 On tree line West

Signed by John C. Bueche
 John C. Bueche
 Surveyor's Michigan License No. 13027

Date 10-10-94



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1974
 REVISED MAY 14, 1975
 REVISED JAN., 1993

LIBR.0005 PAGE 035