

# SURVEY & REMONUMENTATION

APR 25 1995

## Allegan County Remonumentation LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

**COMMISSION**  
Allegan  
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>13W</u>	<u>K-3(SE, 2)</u>
	T _____ R _____	<u>Salem Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1994 DEC 16 AM 9:56  
*John C. Bueche*  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY MICHIGAN  
**FILED**  
 Register of Deeds Stamp & File Number

I, John C. Bueche, in a field survey on September 29, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- K-3 Set post LCRC-L2, P360, Jan., 1975 Holland Eng. No date
  - B. Ash 9" Found 1" pipe Same as LCRC L2, P360
  - N 88° W 90 lks SW cor. blk. bldg. T.K.A. No date
  - Sergum 20" S 40° E 83.75' Same as LCRC L2, P360
  - N 4° W 20 lks Rd. sign N 45° E 56.20' Co. Surveyor 1976
  - Jan., 1832 TP N 45° W 60.67' Raised with bolt
  - L. Lyon, D.S. 1981 Survey 81-6857

OVER

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-3 Found bt. spk. in bit. rd.  
 C/L 36" CMP (N end) NW 47.0'  
 C/L 36" CMP (S end) SW 38.75'  
 PK Nail in S side PP S 70° E 144.42'  
 C/L Rd. E-W 4'± N  
 C/L Rd. N-S 2'± W


And is accepted as a careful and faithful perpetuation of the position of the original corner

APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 10-11-94  
 COUNTY REP. *Richard Van Dyke*

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-3 Replaced bt. spk. with 3/4" x 24" pin with Allegan Co. Remon. Cap  
 Nail & Allegan Co. Remon. Tag in S side PP S 70° E 144.28'  
 Nail & Allegan Co. Remon. Tag in SE side 26" Ash S 55° W 81.85'  
 Nail & Allegan Co. Remon. Tag in S side PP N 55° W 167.84'  
 Nail & Allegan Co. Remon. Tag in SW side 32" Oak N 30° W 167.46'  
 NW cor. conc. walk S 50° E 115.27'  
 C/L bit. S & gravel N Rd. W 2'±  
 C/L bit. E-W N 3.5'±  
 Meas. by EDM

Signed by John C. Bueche Date 10-10-94  
 Surveyor's Michigan License No. 13027



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983

*Allegan*

PART A

Rd. sign NE 56.2'  
C/L 36" CMP (N end) NW 47.0'  
C/L 36" CMP (S end) SW 38.75'

K-3

Jonker 1990

C/L E-W Rd. 4' N

C/L N-S Rd. 2' W

Set Nail in NW side 10" Box Elder S 40° W 62.04'

Stop sign S 20° E 48.1'

Set Pk in E side sign post N 30° E 55.64'

Stop sign N 30° W 47.0'

Jonker 1990

Bt. spk.

Nail in E side 10" Ash S 35° W 62.04'

PK Nail in S side PP S 70° E 144.42'

PK Nail in E side sign post N 35° E 55.65'

REPRODUCED FROM THE ORIGINAL RECORDS OF THE  
ALLEGAN COUNTY ENGINEER  
ALLEGAN COUNTY ENGINEER  
ALLEGAN COUNTY ENGINEER  
ALLEGAN COUNTY ENGINEER