

APR 29 1998

SECTION

Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBERO 007 PAGE 77

For corners in

Allegan (County)	Located In:	Corner Code #
1. Public Land Survey	T 4N R 13W	K-9 (NW, 25) Salem Twp.
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED

1/28/1999 2:44:39 PM

JOYCE A. MATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

I, John C. Bueche, in a field survey on April 2, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-9 GLO, April, 1831	LCRC 1-384, July, 1972, Ratekin	
Calvin Britain	Set 1" iron by extending line	
Set post Secs. 23, 24, 25 & 26	from SE cor. over S 1/4	
W. Oak 15" S 51 W 3	post West 80.08' (5285.25')	
Beech 8" N 63 E 15	Chains from SE cor. as per	
1897 Hugh McDougal	old Govt. notes	26" Twin Oak N 60° E 61.05'
This cor. on line S 1/4 & SW	PP S 65° W 63.45'	on East edge N-S road
Sec. 24 & both 1/2 miles	PP N 35° E 39.30'	<u>OVER</u>
dist. to be 2642.5'		

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-9 Found capped (can not read) rerod in Mon. Box 1± E. of N-S bit. road;
5± South E-W gravel road Did not find iron NE 12.83'
As per LCRC 3-245 & survey 1025-469

And is accepted as a careful and faithful perpetuation of the position of the original corner.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED APRIL 14, 1998
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9 Replaced rerod with 3/4" x 24" pin with Allegan Co. cap in Mon. Box
Nail & Allegan Co. Remon. Tag in N side PP S 65° W 51.21'
Nail & Allegan Co. Remon. Tag in SE side PP N 50° E 52.06'
Nail & Allegan Co. Remon. Tag in W side 36" Maple S 20° E 94.44'
Nail & Allegan Co. Remon. Tag in S side 32" Oak N 70° E 75.22'
Nail & Allegan Co. Remon. Tag in W side 18" Oak N 30° E 95.04'
C/L bit. road N-S, West 1±; C/L gravel road E-W, North 5±



Signed by John C. Bueche Date 4-13-98
John C. Bueche, P.S. 13027
Surveyor's Michigan License No. _____

APR 29 1980

SECTION

K-9 SALEM TWP.
PART A - CONTINUED

LCRC 3-245, April, 1979

Fnd. 1/8" x 2 1/2" flat iron with bricks around it

Very near position; found iron 12.83' ENE previously recorded erroneously
PK in side service pole NE 51.95'

PK in side PP SE 51.15'

Cement nail in side 36" Oak NNW 98.44'

Cement nail in side 14" Twin Oak ENE 75.17'

1" iron NE 12.83'

C/L gravel 5'± N & 3.5'± W

Survey L1025, P469, Sept., 1982

Fnd. 1/2" rerod, Jonker

PK on NW side PP S 70° W 51.08'

PK on NW side PP N 45° E 52.04'

Spk. on S side Twin 36" Oak N 60° E 75.27'

3/4" solid iron N 10° E (N 60° E) 12.83'

LIBERO 007 PAGED 78