

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN (County)	Located In:	Corner Code #
1. Public Land Survey	T-4N R-13W	K-13 (SW, 36)
	T R	SALEM TWP
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

1995 DEC 14 PM 2:36
 Register of Deeds Stamp & File Number
 F11 F11

SURVEY & REMONUMENTATION COMMISSION
 APR 29 1996

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, BASIL ADDRESS, in a field survey on 16 MAR, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration.

G.L.O.
 WEST ON S SIDE SEC- 36 T-4N, R-13W
 80.00 SET POST COR SECTIONS 35 & 36
 BEECH 8" N 35° E 91 LKS
 BEECH 9" N 75° W 31 LKS

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 3-14-95
 COUNTY REP. [Signature]

CONT. ON BACK OF CERTIFICATE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD MON. BOX - NO IRON
 1" IRON IN MON BOX (NW COR SEC-1, MONTEREY TWP)
 PULLED '93 WITNESSES (JONKER) THEY CROSSED AT OUTER EDGE OF MON. BOX - JOG
 MEAS. 18.83' SET STD. ALLEGAN CO. MON. IN MON. BOX @ G.L.O. JOG OF
 29 LKS - 19.14'
 THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE
 POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

STD. ALLEGAN CO. MON. (3/4" X 24" PIN & CAP) IN MON. BOX
 16d & REMON TAG SE SDE 28" OAK S 55° W 52.93'
 16d & REMON TAG NE SDE PP S 55° E 58.36'
 16d & REMON TAG N SDE PP N 55° W 102.47'
 16d & REMON TAG S SDE 42" OAK N 70° E 74.18'
 TOP NW COR CONC BLK FND (HSE #2595) N 40° E 154.47'
 1" IRON IN MON BOX (K-1, MONTEREY TWP) WEST 19.14'
 C/L 26TH ST EAST 3'±
 IN C/L 136TH AVE
 STD. ALLEGAN CO. MON (S 1/4 COR, SEC-36, SALEM TWP) EAST 2643.28'



Signed by [Signature] Date 21 APR 95
 Surveyor's Michigan License No. 30075

LIBR 0005 PAGE 286

SHEET 1 OF 2

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION.

OCT., 1887 HUGH MACDOUGAL, C.S.
 NOTES CALL FOR STONE
 OAK 6" NE 46'
 OAK 3" NE 56'
 DIST W TO $\frac{1}{2}$ COR 2658'
 DIST N TO $\frac{1}{2}$ COR 2648 $\frac{1}{2}$ '

MAR., 1911 HUGH MACDOUGAL, C.S.
 FD STONE
 DIST E TO $\frac{1}{2}$ COR 2650.4'

NOV., 1971 DOUGLAS W. BONNEMA, P.S.
 L.C.R.C. L- 001, P- 159
 REESTABLISHED OBLITERATED CORNER BY
 EXISTING PHYSICAL EVIDENCE
 SET 5/8" IRON ROD
 18" OAK SSW 83.49'
 24" HICKORY SW 51.76'
 20" OAK NW 61.85'
 40" OAK NE 48.79'
 1" IRON PIPE W 19.14'

APR., 1972 DONALD A. RATEKIN, C.S.
 L.C.R.C.

1993 ROBERT JONKER
 SET IRON W/ CAP OVER 3/4" IRON
 FD NAIL S SDE 36" OAK N 75° E 74.25'
 FD NAIL S SDE 36" OAK S 55° W 52.8'
 FD NAIL NE SDE PP S 55° E 58.35'
 DIST E TO $\frac{1}{2}$ COR 2643.32'