

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

1095 DEC 14 PM 2:37
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
Spencer W. ...

FILED

For corners in
ALLEGAN (County) Located In: Corner Code #:

1. Public Land Survey T-4N R-13W L-13 (St., 36)
 T R SALEM TWP
 T R
 T R
 T R
 S T R
 S T R
 S T R
 S T R

2. Property Controlling in Section
 3. Miscellaneous Property in Sec.
 4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

SURVEY &
 REMONUMENTATION
 APR 29 1996
 COMMISSION

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

1. BASIL ADDRESS in a field survey on 16 MAR 19 95
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.
 WEST ON S. SIDE SEC- 36, T-4N, R-13W
 40.00 SET QR. SEC. COR
 BEECH 7" N 80 E 37 LKS
 BEECH 5" N 86 W 18 LKS

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 8-14-95
 COUNTY REP. Basil J. Andress

CONT. ON BACK OF CERTIFICATE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD 1/2" IRON W/ CAP
 CHK'D W. JONKER'S WITNESSES
 DIST WEST TO K-13 (SALEM TWP) 2643.28'
 FD 1 1/2" IRON (N 1/2, SEC-1, MONTEREY TWP) WEST 9.50'
 FD 3/4" PIPE (FALSE CORNER, PULLED) EAST 2.5'

THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED 1/2" IRON W/ CAP W/ STD. ALLEGAN CO. MON. (3/4" X 24" PIN & CAP)
 16d & REMON TAG W ROOT 26" OAK N 05° E 117.42'
 16d & REMON TAG SE ROOT 18" OAK N 45° E 75.88'
 16NDN & REMON TAG SW SDE 8" PINE S 45° E 47.04'
 16d & REMON TAG SE SDE 16" OAK S 45° W 80.06'
 16d & REMON TAG NE SDE TWIN 12" OAKS N 65° W 74.58'
 16d & REMON TAG W SDE 14" OAK S 15° W 67.53'

C/L 136TH AVE SOUTH 7'±
 STD. ALLEGAN CO. MON. (N 1/2 COR SEC-1 MONTEREY) WEST 9.57'
 STD. ALLEGAN CO. MON (SW COR, SEC-36, SALEM TWP) WEST 2643.28'



Signed by Basil J. Andress Date 21 APR 95
 Surveyor's Michigan License No. 30075

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION.

1911 HUGH MACDOUGAL, C.S.
 STAKE
 OAK 18" SW 22.2'
 OAK 14" SE 21.7'
 OAK 20" NE 31.7'
 DIST E TO SEC COR 2650.4'
 DIST W TO SEC COR 2650.4'

1983 RAY MOORED, P.S.
 FD ½" IRON W. CAP
 ANGLE IRON E 2.5'
 IN LINE W/ FE TO NORTH
 IN LINE W/ C/L DR TO NE
 C/L 34" OAK N 60° E 34.0'
 C/L 16" OAK S 45° E 35.0'

1987 BRIAN REYNOLDS
 FD ¼" CAPPED IRON
 8" OAK S 60° E 71.93'
 16" OAK S 30° W 30.21'
 PIPE EAST 2.5'

1988 GORDEN D. NEDERVELD, P.S.
 CAPPED IRON
 IRON WEST 7.06'
 1" SOLID IRON WEST 9.51'
 NAIL S SDE 30" OAK NE 34.94'
 NAIL E SDE 14" OAK SW 35.20'
 NAIL N SDE 30" OAK SW 95.65'
 C/L GRAVEL RD (136TH AVE) S 7'±

1992 ROBERT J. JONKER, P.S.
 CAPPED IRON
 NAIL S. SDE 30" OAK NE 34.94'
 NAIL E SDE 14" OAK SW 35.20'
 NAIL N SDE 30" OAK SW 95.65'

1993 ROBERT J. JONKER, P.S.
 CAPPED IRON
 C/L E - W RD (136TH AVE) 7'± S
 FD NAIL W SDE 18" OAK S 40° W 35.77'
 FD NAIL S SDE 36" OAK N 60° E 34.80'
 FD NAIL S SDE 12" OAK S 60° E 63.11'
 IRON NORTH 32.97'
 DIST E TO SEC COR - 2643.67'
 DIST W TO SEC COR - 2643.32'