

Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970.

For corners in

Allegan
(County)

Located in:
Dorr Twp.

Corner Code ##

1. Public Land Survey	T <u>4N</u> R <u>12W</u>	<u>A-1</u>
	T <u>4N</u> R <u>13W</u>	<u>(m-1 SALEM)</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Robert J. Jonker
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.

1994 DEC 16 AM 9:56

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert Jonker, in a field survey on August 06, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. survey, 1826 No info. of value from any old Corner common to 4 Twps.
Beech 10", S 71° E 41' County Surveyors notes or from
Beech 13"; N 22° E 28' the Road Commission.

C.P. Co. wit. 1976, Fd. "T" Iron L.C.R.C., Liber 3, Pg. 267.
SW cor. h/w N 30° W 34.8' Nederveld & Jonker, 1979 (OVER)
SE cor. h/s N 30° E 33.25' "T" Iron per C.P. Co. wit.
W. end metal Culv. S 30° W 37.07' PK in SE side P.pole NE 62.55'
PK in W. side P.pole SSE 79.20'
Nail W. side 12" Walnut NNE 43.70'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 4" dia. cast iron monument (Harrison) mon. set by Kent Co. at the corner of Byron Twp.
Per L.C.R.C., Liber 3, Page 267
PK W. side P.pole SSE 79.20'
Nail W. side 12" Walnut NNE 43.70'

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 8-9-94
COUNTY REP. *Robert J. Jonker*

ROY L 1995
COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

4" Cast Iron Harrison Monument
Allegan Co. N&T W. side 16" Walnut Az. 30° 43.62'
Allegan Co. N&T N. side G.pole Az. 65° 62.45'
PK Nail W. side P.pole Az. 155° 79.36'
C/L E-W pavement is South 3'±
on C/L N-S gravel



Accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by Robert J. Jonker Date August 09, 1994
Surveyor's Michigan License No. JONKER LAND SURVEYS 21572

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 24, 1971
REVISED MAY 14, 1975
REVISED JAN., 1993

LIB# 0005 PAGE 077

A-13, T5N, R12W

Recorded by LCRC's #37, 1509, 4634

LCRC #37, W & W, 1971, looked for stone, did not find, found spk. 2' down
@ C/L "X", accepted, set "T" iron

LCRC #1509, W & W, 1980

Found "T" iron, set K.C. monument

LCRC #4634, Bueche, 1988

Remon. maint.

SURVEY &
REMONUMENTATION

NOV 10 1995

COMMISSION