

**SURVEY
REMONUMENTATION**

APR 29 1999

SECTION

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

LIBR0007 PAGE 25

For corners in <u>Allegan</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T4N R14W	A-5
	T _____ R _____	_____
	T _____ R _____	NW corner
	T _____ R _____	Section 18
2. Property Controlling in Section	S _____ T _____ R _____	Overisel Twp.
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Steve Lampen, in a field survey on December 19, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-5	County Records
GLO - Britain-Brookfield - 1831-1832	Iron
West between Sections 7 and 18 72.64	Telephone pole SE 58.74
West boundary 98 S of post and set	Power pole NW 46.78
Corner to Sections 7 and 18	SW corner house NE 87.1
Pine 10 S 73 E 11	9" Maple ENE 49.25
Hemlock 3 N 35 E 22	9" Maple NE 61.56

Survey - 1986 - VanOrder
Found iron in monument box
NW corner house foundation NE 87.2
Telephone pole SE 58.57
A-5 to A-6 = 2635.54

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-5 Found 3/4" iron in monument box on the East line of Section 13, Town 4 North, Range 15 West
NW corner house foundation NE 87.2 A-5 to A-6 rec. = 2635.54 meas. = 2635.69

Replaced iron with 3/4"x24" Allegan County Remonumentation iron and cap and accepted it as a careful and Faithful perpetuation of the position of the original corner.

Traversed 2646 ft. on road.

A-5 was approved by the Allegan County Remonumentation Peer Group on December 22, 1998.

APPROVED REMONUMENTATION CORNER

P.A. 345 OF 1990

ALLEGAN COUNTY

DATE APPROVED DEC. 22, 1998

COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5 3/4"x24" Allegan County Remonumentation iron and cap in monument box on the East line of Section 13,

Town 4 North, Range 15 West

Azimuth = Michigan State Plane grid direction

Guy pole, remonumentation tag in NW side	340° 20'	122.81
Power pole, remonumentation tag in W side	13° 04'	107.20
Power pole, remonumentation tag in SE side	300° 49'	44.90
NW corner porch foundation	62° 01'	87.26
M-5, Town 4 North, Range 15 West	359° 05'	64.69

Signed by Steven Lampen

Date JANUARY 11, 1999

Surveyor's Michigan License No. 37279

