

APR 29 1999

SECTION

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>Allegan</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T4N R14W	B-9
	T R	
	T R	North 1/4 corner
	T R	Section 30
2. Property Controlling in Section	S T R	Overisel Twp.
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

LIBR0007 PAGE031

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Steve Lampen, in a field survey on December 19, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 B-9 Consumers Power Co. - Survey 1968  
 GLO - Britain-Brookfield - 1831-1832 Found railroad spike  
 Set 1/2 mile post Set 1" iron  
 Beech 10 S 55 W 5 Telephone pole NW 41.5  
 White Ash 12 East 11 Power pole NE 54.0  
 Telephone pole ENE 59.3  
 B-9 to A-9 = 2322.33 S end headwall SW corner ESE 51.7  
 B-9 to C-9 = 2641.14 S end headwall SE corner WSW 48.5  
 B-9 is 6.12' South of A-9 to C-9

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9	●												
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

L.C.R.C. L1, P332 - 1972 Ratekin  
 Found 1" iron  
 Telephone pole N 45° W 41.5  
 Power pole N 50° E 54.0  
 SW corner headwall S 70° E 51.7  
 SE corner headwall S 70° W 48.5

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 B-9 Found 1" pipe in monument box Power pole NE 54.0  
 B-9 to A-9 rec. = 2322.33 meas. = 2322.58 B-9 to C-9 rec. = 2641.14 meas. = 2641.01  
 B-9 is South of A-9 to C-9 rec. = 6.12 meas. = 6.05

Replaced pipe with 3/4"x24" Allegan County Remonumentation iron and cap and accepted it as a careful and faithful perpetuation of the position of the original corner.

B-9 was approved by the Allegan County Remonumentation Peer Group on December 22, 1998.

APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED DEC. 22, 1998  
 COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 B-9 3/4"x24" Allegan County Remonumentation iron and cap in monument  
 Power pole, remonumentation tag in NE side 151° 48' 97.29  
 Power pole, remonumentation tag in SE side 54° 59' 54.72  
 Power pole, remonumentation tag in W side 6° 13' 363.36  
 Power pole, remonumentation tag in S side 280° 49' 323.67



Signed by Steven Lampen Date JANUARY 11, 1999  
 Surveyor's Michigan License No. 37279