

APR 29 1999

SECTION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

LIBERO 007 PAGE 032

For corners in Allegan (County) Located In: Corner Code #
1. Public Land Survey T4N R14W B-10
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

1/28/1999 2:44:39 PM
JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH
Register of Deeds Stamp & File Number

I, Steve Lampen, in a field survey on December 19, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-10
GLO - corner not monumented by GLO
L.C.R.C. - L5, P176 - 1995
Set 3/4" iron at the intersection of the 1/4 lines
X cut South end of 18" CMP 123° 56.54
Nail in W face Power pole 150° 71.80
Nail in S face Power pole 204° 64.72
Nail in W face Power pole 11° 184.65
3/4" iron in monument box 0° 2.74

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-10 Found 3/4" iron in monument box Iron in monument box N 2.74
Nail in South face of Power pole 204° 64.72 Nail in W face of Power pole 11° 184.65

Found iron to be 0.05' South of intersection of 1/4 lines, set 3/4"x24" Allegan County Remonumentation iron And cap at the intersection of the 1/4 lines. This corner was not monumented by the original GLO Survey. Set iron is accepted as the best evidence of the position of the corner.

Traversed 7927 ft on road, 2364 ft. off road.

B-10 was approved by the Allegan County Remonumentation Peer Group on December 22, 1998.

APPROVED REMONUMENTATION CORNER

P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED DEC. 22, 1998
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-10 3/4"x24" Allegan County Remonumentation iron in monument box at the intersection of the 1/4 lines.
Azimuth = Michigan State Plane grid direction
Power pole, remonumentation tag in SW side 148° 52' 72.36
Guy pole, remonumentation tag in E side 203° 24' 64.76
Power pole, remonumentation tag W side 9° 58' 184.69
SE corner house #3415 344° 33' 377.86

B-9 = 359° 02' 17" 2639.14 C-10 = 92° 31' 50" 2653.85
B-11 = 179° 02' 17" 2633.75 A-10 = 272° 31' 50" 2364.01

Signed by Steven Lampen Date JANUARY 11, 1999

Surveyor's Michigan License No. 37279

