

REMONUMENTATION

APR 24 1995

COMMISSION

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan (County)	Located In:	Corner Code #
1. Public Land Survey	T 4N R 14W	C-8 (W 1/4 Sec 20)
	T R	Overisel Twp.
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

1994 JUN -3 PM 1:17
 Register of Deeds Stamp & File Number

FILED

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Gerald T. Ford, in a field survey on November 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Monument	Subsequent Restoration
C-8	C-8
1831	Consumers Power Co. Witnesses (Drawing No SF-16897)
Government Land Office Survey Notes	1" Iron Rod 25' W of Stone
Post	Telephone Pole
8" Beech N17°W 29 links	NE 48'
8" Sugar S33°E 25 links	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-8
 Found stone and accepted it as a careful and faithful perpetuation of the position of the original corner.

1" Steel Bar	N	0.4'
1 1/4" Steel Bar	W	0.5'

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 12-14-93
 COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-8
 Replaced stone with A.C. Remonumentation Iron and Cap

"X" cut in top fnd plate (2' above grd) W leg C.P. Co. Trans. Tower	AZ. 22°	316.93'
"X" cut in top fnd plate (2' above grd) S leg C.P. Co. Trans. Tower	AZ. 27°	308.45'
A.C. Remon tag & nail in N face 6" Elm	AZ. 88°	44.68'
A.C. Remon tag & nail in S face 3" Elm	AZ. 93°	43.28'



Signed by Gerald T. Ford Date January 21, 1994
 Surveyor's Michigan License No. 33976

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 21, 1971
 REVISED MAY 14, 1976
 REVISED JAN., 1981