

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in _____

_____ Allegan (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>14W</u>	<u>D-8 (Center-Sec-20)</u>
	T _____ R _____	<u>Overisel Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED
 1993 DEC 30 PM 2:41
Joyce A. Patton
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Gerald T. Ford, in a field survey on December 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-8
 No previous record

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-8
 Set Allegan County remonumentation iron and cap at the intersection of 1/4 lines. This position not established by original government surveyors. This monument is accepted it as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-8
 Set Allegan County remonumentation iron and cap
- | | | | |
|---|-----|------|--------|
| Set "X" cut in top of North end 24" conc. culvert | AZ. | 57° | 60.97' |
| Set "X" cut in top of South end 24" conc. culvert | AZ. | 111° | 56.65' |
| Set "X" cut in top of North end 12" CMP culvert | AZ. | 336° | 70.10' |
| Set "X" cut in top of South end 18" CMP culvert | AZ. | 316° | 40.25' |



Signed by Gerald T. Ford Date December 13, 1993

Surveyor's Michigan License No. 33976