

COMMISSION  
For corners in

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1993 DEC 30 PM 2:45  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.  
FILED

Allegan (County) Located In: Corner Code #/

1. Public Land Survey T 4N R 14W —D-9(S-1/4—Sec 20)  
T \_\_\_\_\_ R \_\_\_\_\_ —Ovenisel Twp.  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Gerald T. Ford, in a field survey on November 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-9				Recorded in Liber 3, Page 335, June 9, 1982
1831				Steel Bar
Government Land Office Survey Notes				Nail in Power Pole NW 75.67'
Post				Nail in Telephone Pole NE 50.67'
9" Sugar N31°W	19 links			Nail in 28" Maple SW 124.44'
20" Beech S41°E	18 links			NE Corner House SW 146.04'
				Street Sign SSW 27.28'
				CL N-S Road E 12.00' ±

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-9  
Found 5/8" steel bar in monument and accepted it as a careful and faithful perpetuation of the position of the original corner  
NE Corner House SW 145.79'  
PK & tag W face PP NW 75.72'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-9				
Replaced iron in monument box with A.C. remonumentation iron & cap				
Cross in brass table #2 in conc. Azimuth mark Meiste #2	AZ.	328°	76.96'	
A.C. Remon tag & nail in North face 6" Maple	AZ.	246°	106.61'	
NE Cor conc.. house foundation	AZ.	204°	145.79'	
A.C. Remon tag & nail in East face 7" Maple	AZ.	182°	138.79'	
A.C. Remon tag & nail in West face 3" Maple	AZ.	226°	78.30'	



Signed by Gerald T. Ford Date December 21, 1993  
Surveyor's Michigan License No. 33976