

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Allegan</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 4N R 14W	D-11
	T _____ R _____	S 1/4 Cor.
	T _____ R _____	Sec. 29
	T _____ R _____	N 1/4 Cor.
2. Property Controlling in Section	S _____ T _____ R _____	Sec. 32
	S _____ T _____ R _____	Overisel Twp.
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
 1994 DEC 30 PM 12:18
 FILED

Register of Deeds Stamp & File Number

I, Kirk Van Order, in a field survey on March 14, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

A. Description of original monument and accessories and/or subsequent restoration:

D-11

•GLO set post at 40.10 chains West of E-11.

30" Elm S35°W 29 links
10" Birch S33°E 25 links

•LCRC (L. 3, P. 335) 3-11-1982

Set iron from field evidence pipeline marker	S,SE	326.65'
Witness iron	E	50.00'
Witness iron	E	100.00'
Witness iron	W	50.00'
Witness iron	W	100.00'

(Continued on
back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-11

Fd. tire iron 3-14-94

Fd. 1/2" rerods 50.00' and 100' West

Fd. 1/2" rerod 50.21' East and 100'+/- East in ditch below water

John P. Clapp set point by extending a line North from an iron set by M.V.K., South of the center of Section 32 thru the center of said Section as monumented to a field division line running to the East and West.

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group approved 8-9-94.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 8-9-94
 COUNTY REP. Kirk Van Order

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-11

Removed tire iron and set standard Allegan Co. Remon. monument (3/4" x 36" steel rod w/red cap #23520)

Nail and Remon. tag in N side 4" Ash	AZ. 273°41'05"	377.49'
Set capped Remon witness iron 3/4" x 36"	AZ. 93°00'00"	50.00'
Set capped Remon. witness iron 3/4" x 36"	AZ. 273°00'00"	50.00'
NW face ANR pipeline pipe marker post	AZ. 176°14'40"	326.43'
C/L gravel road	AZ. 90°00'00"	4'+/-
North 1/4 corner Section 29	AZ. 00°00'00"	5271.84'

Signed by _____

Date 12-30-94

Surveyor's Michigan License No. 23520

USER 0005 PAGE 150

Page 1 of 2

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

Section A (continued from Page 1)D-11

- Holland Engineering, Inc. witness card shows a tire iron was set, JPC 82.
All other witnesses same as LCRC.
- K.V.O. survey shows a 1" pipe found (tire iron)
C/L gravel 45th St. E 4'+/-
Ditch line to the East pipeline marker post S,SE 326.65'
Field line to the West