

**SURVEY
REMONUMENTATION**

APR 29 1999

SECTION

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Allegan</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T4N R 14W	E-11
	T___ R___	<u>Overisel</u> Twp.
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

FILED
1/28/1999 2:44:39 PM
JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

LIBERO 007 PAGE 034

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk L. Van Order, in a field survey on Mar. 25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-11

- (1) GLO
North between Sections 32 & 33
80.00 chains set post corners of Sections 28, 29, 32 & 33
Beech 3" N12°W 5 links
Beech 8" S12°W 5 links
- (2) John P. Clapp recorded LCRC, Liber 003, Page 332, dated Mar. 11, 1982
Fd. 1" iron pipe from county surveyor witness ties

(continued on back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-11

Fd. 1" x 1.15' steel pipe using the witness ties listed in No. 2 of above. And is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer group approved Nov. 24, 1998.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED NOV. 24, 1998
COUNTY REP. [Signature]


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11

Replaced pipe with standard Allegan Co. Remon. monument (3/4" x 36" steel rod w/red cap #23520)

Nail & Remon. tag in SE side 53" poplar	AZ 245°	27.54'
Nail & Remon. tag in NE side 38" maple	AZ 340°	96.88'
NE corner conc. fndn. to corn crib	AZ 260°	63.80'
SE corner of house conc. block fndn.	AZ 310°	126.00'

Signed by [Signature]
Surveyor's Michigan License No. 23520



Date 12-23-98

SURVEY
REMONUMENTATION

APR 29 1990

SECTION

LIBERO 007 PAGE 35

Section A (continued from Page 1)

E-11

Overisel Twp., T.4N., R. 14W.

(Continued No. 2)

Corner corn crib	W,SW	63.60'
Corner shed	SW	62.30'
Nail in tel. pole	SW	40.95'
Nail in 50" poplar	W,SW	27.37'
Nail in 6" cherry	E,NE	22.23'

- (3) Kirk L. Van Order, R.L.S. survey recorded in Liber 1074, Page 243, dated June 14, 1984

Fd. 1" steel rod		
C/L tele. pedestal	SW	41.0'
NE cor. shed	SW	62.4'
NE cor. corn crib	W,SW	63.6'
C/L gravel 44th St.	East	3'

- (4) Kirk L. Van Order survey dated Mar. 14, 1989

Fd. 1-1/4" pipe		
48" poplar	W,SW	27.52'
C/L top tel. ped.	SW	40.63'
NE cor. conc. fnd.	W,SW	63.79'
SE cor. porch fnd.	NW	125.80'

- (5) Kirk L. Van Order survey dated Feb. 19, 1996

Fd. 1-1/4" pipe
(same ties as in No. 4)