

Allegan County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Allegan Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T4N R14W F-3 (S 1/4, Sec. 4)  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

97 JAN 22 PM 1:27  
 FILED  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Steven Lampen, in a field survey on November 19, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumanted, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 F-3 Old Notes at County Surveyors Office  
 GLO - Britain - 1832 2636.2' W from G-3  
 Britain 1832 Street sign SW 15.2'  
 Set 1/4 section post Fence post NE 33.2'  
 Sugar 12' N 68' E 25' Concrete block building NW 111.2'  
 Do 10' S 58' W 24'

Consumers Power Co., 1968  
 By Don Ratekin  
 1" iron  
 Street sign W 15.2'  
 Fence NE 30.2'  
 Concrete Block Bldg NW 111.2'


1976 Survey Consumers Power Company  
 Found pipe from witnesses Wightman Meored Survey 1990  
 Road sign S 87 $\frac{1}{2}$  W 15.35' 2673.62 W from SE corner  
 Telephone riser box S 45 $\frac{1}{2}$  E 46.30'  
 SE corner block building NW 111.31' Gardner - 1880  
 E-3 W 2640'  
 G-3 E 2636.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 F-3  
 Found 1/2" bar in monument box  
 SE corner block building NW 111.31'  
 Found 1/2" iron in monument box is accepted as a careful and faithful perpetuation of the original corner.  
 Replaced 1/2" iron with 3/4"x24" Allegan County Remon. and Remon. cap.  
 Approved by Allegan County Surveyors Peer Group on November 26, 1996.

APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 11-26-96  
 COUNTY REP. *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 F-3  
 3/4"x24" Allegan County Remon. iron and Remon. cap in monument box.

Telephone pole Remon. tag SE side 16' E 99.29'  
 SE corner brick foundation house 338' 236.11'  
 SE corner brick building 325' 111.34'  
 Telephone pole Remon. tag E side 203' 218.40'  
 Center Michigan Bell box 141' 46.65'



Signed by Steven Lampen Date December 12, 1996  
 Surveyor's Michigan License No. 37279