

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Allegan (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>14W</u>	<u>G-2 (E-1/4-4-4)</u>
	T _____ R _____	<u>Overisel-Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
Joyce A. Ceballos

1993 DEC 30 PM 2:45

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Gerald T. Ford, in a field survey on November 18, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- | | | | | |
|--|-----|---------------------------------|---|----------|
| G-2 - 1831 | | C.P. Co. (Drawing No. SF-17935) | | |
| Government Land Office Survey Notes | | Center, Sec 4, T4N, R14W | W | 2668.45' |
| 20" Beech for corner No witnesses. | | | | |
| G-2 | | Holland Engineering, Inc. | | |
| Recorded in Liber 3, Page 345, Nov. 17, 1982 | | E 1/4 Cor. Sec. 3, T4N, R14W | E | 5355.12' |
| NW Cor Steel Bldg | SE | 194.23' | N | 2822.40' |
| Nail S Side 8" Box Elder | W | 46.44' | | |
| "X" in East end CMP Culvert | NNE | 110.55' | | |
| CL Blacktop Road | E | 0.5' | | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-2
 Field evidence suggests that wrong corner was inadvertently recorded in Liber 3, Page 245.
 Found lag screw in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner.
- | | | |
|--|---|----------|
| Meas. dist. to NE Cor, Sec 4, Found steel bar | N | 2822.40' |
| Meas. dist. to E 1/4 Cor, Sec. 3, Found steel bar | E | 5355.12' |
| Meas. dist. to Center, Sec. 4, Found steel bar in mon. box | W | 2668.40' |

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-2
 Replaced lag screw in monument box with A.C. remonumentation iron & cap
- | | | | |
|--|-----|------|---------|
| A.C. Remon tag & nail in SW face of Power Pole | AZ. | 308° | 85.12' |
| A.C. Remon tag & nail in S face of Power Pole | AZ. | 71° | 158.21' |
| "X" cut in top of N end of 18" CMP Culvert | AZ. | 69° | 64.65' |
| "X" cut in top of S end of 18" CMP Culvert | AZ. | 115° | 63.29' |



Signed by Gerald T. Ford Date December 21, 1993
 Surveyor's Michigan License No. 33976

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

W:\Deeds\Surv\Remon.fec

LIBER 004 PAGE 343