

SURVEY &
REMONUMENTATION

APR 07 1998

SECTION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>14W</u>	<u>G-3</u>
	T <u> </u> R <u> </u>	<u>Sec. 3, 4,</u>
	T <u> </u> R <u> </u>	<u>9 & 10 Cor.</u>
	T <u> </u> R <u> </u>	<u>Overisel Twp.</u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

98 JAN 21 PM 1:35
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
Joyce L. Estlin

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kirk L. Van Order, in a field survey on June 10, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- G-3
 (1) GLO Calvin Britain D.S., 1831
 North between Sec.s 9 & 10
 80.00 ch. Set post cor. Sec.s 3, 4, 9 & 10
 Beech 10" N74°W 6 links
 Beech 8" S23°E 13 links
 (2) E. P. Waterman field notes, Oct. 1, 1891
 Stone (no ties) (continued on back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-3
 (1) Kirk L. Van Order Remon. survey dated June 10, 1997
 Pd. capped 1/2" re-rod using tie info. from Part A, Item No. 9. And is accepted as a careful and faithful perpetuation of the position of the original corner.
 Peer group approved June 10, 1997.

APPROVED REMONUMENTATION CORNER
 P.A. 343 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 6-10-97
 COUNTY REP. K.V.O.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-3
 * Note: Remon. iron to be set after road construction
 Nail & Remon. tag in NW side p. pole AZ 44°-00' 125.27'
 SE cor. conc. block hse. fndn. AZ 208°-48'10" 146.52'
 NE cor. conc. block hse. fndn. AZ 215°-33'55" 123.36'
 NW cor. conc. porch floor AZ 225°-49'-23" 135.86'

Signed by *Kirk L. Van Order*
 Surveyor's Michigan License No. 23520

Date 12-31-97

USEP 0006 PAGE 187

Section A (continued from Page 1)

G-3

Overisel Twp., T.4N., R.14W.

- (3) D.A. Ratekin tie sheet, 1968
 Fd. stone, lowered set iron over
 Tw. Cherries 10" S.,SE 26.0'
 Cherry 42" SW 42.6'
 P.P. NW 27.51'
 Cherry 10" SW 89.60'
- (4) H.E.I. survey, Aug. 27, 1980, L. 990, P. 424
 Fd. 5/8" steel bar
 Cherry 42" SW 43.70'
 Power pole NW 28.25'
 Cherry 10" SW 89.80'
 Power pole NE 125.34'
- (5) Wightman-Moored field notes, Aug. 7, 1990
 Fd. iron (no ties)
- (6) Wightman-Moored survey, Aug. 8, 1990
 No description, no ties
- (7) Wightman-Moored survey, Aug. 15, 1990
 No description, no ties
 Show fd. iron at SW R.O.W.
- (8) Wightman-Moored field notes, Feb. 12, 1991
 Fd. capped iron
 Cherry 14" S75°W 89.76'
 Maple 48" S45°W 43.71'
 P.P. S20°E 37.39'
 C/L road to South W 4'
- (9) Kirk L. Van Order survey for A.C.R.C. dated Nov. 13, 1996
 Fd. capped 1/2" re-rod, unable to read number on top
 NE cor. conc. block hse. fndn. SW 123.35'
 NW cor. conc. floor of porch SW 135.85'
 Fd. nail & tag No. 14091 in SE side p. pole NE 125.22'
 Fd. nail & tag C.P.C. Prop. in NE side p. pole SE 37.40'
 H-3 AZ 91°-15'-25" 2680.80'
 I-3 AZ 91°-08'-10" 5363.29'
 F-3 AZ 270°-57'-35" 2673.815'