

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Allegan</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>14W</u>	G-9 (SE, 21)
	T <u>   </u> R <u>   </u>	<u>Overisel</u> Twp.
	T <u>   </u> R <u>   </u>	_____
	T <u>   </u> R <u>   </u>	_____
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	_____
	S <u>   </u> T <u>   </u> R <u>   </u>	_____
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	_____
	S <u>   </u> T <u>   </u> R <u>   </u>	_____

97 JAN 22 PM 1:28  
 REGISTERED  
 ALLEGAN COUNTY  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Kirk L. Van Order, in a field survey on Oct. 10, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	19	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- G-9  
 (1) GLO  
 North between Sections 27 & 28 80.00 chains  
 Set post corner of Section 21, 22, 27 & 28  
 Beech 18 N86°E 13  
 Bl Ash 10 S79°W 12  
 (2) Hugh MacDougall Co. Surveyor notes dated May 1, 1905  
 Found stone at corner  
 Maple 6 NW 36.4 (continued on back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9  
 October 10, 1995  
 Found capped iron set by me previously using ties taken July 30, 1990. And is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer group approved May 14, 1996.


APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 5-14-96  
 COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-9  
 Removed capped iron, pipe & mon. box and set standard Allegan Co.  
 Remon. monument (3/4" x 24" steel rod w/red cap #23520)  
 Nail & Remon. tag in NW side 4" Ash AZ 221°48'55" 68.36'  
 Nail & Remon. tag in SW side power pole AZ 298°56'20" 135.86'  
 Punch mark in top steel guard rail post AZ 235°27'05" 157.71'  
 Punch mark in top steel guard rail post AZ 237°08'40" 192.44'  
 C/L asphalt road AZ 180° 3.0'  
 G-10 Remon. Monument AZ 180°00'00" 265'

Signed by [Signature]  
 Surveyor's Michigan License No. 23520

Date 12-31-96



USE 0005 PAGE 499

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, 1971  
 REVISED 11-14-1975  
 REVISED JAN, 1983  
 REVISED OCT, 1985

Section A (continued from Page 1)

G-9

Overisel Twp., T.4N., R.14W.

- Distance East 1312.25' to iron  
 Distance East 2624.50 to stone at N 1/4 corner Section 27  
 Distance South 2654.8' to stone at W 1/4 corner Section 27  
 Distance West 2623.25' to stone at N 1/4 corner Section 28
- (3) Don Ratekin section corner card Section 21, T.4N., R.14W.  
 SE corner Set 3/4" iron from old wit. Nov. 6, 1969  
 Found again 1987  
 Power pole NE 85.10'  
 5" dia. CMP culvert -  
     N. end W.,NW 36.5'  
     S. end W.,SW 37.0'  
 SW cor. tele. box SE 41.50'  
 In C/L of gravel roads
- (4) Wightman-Moored, Inc.  
 ACRC project 140th Ave., dated July 2, 1990  
 Fd. 3/4" iron - set 1/2" pipe w/cap  
 PK in power pole (NW side) NE 85.59'  
 PK in power pole (SW side) NW 137.81'  
 C/L South end of "I" beam  
     post at East end of North  
     guard rail SW 154.47'
- (5) Kirk L. Van Order  
 Fd. 1' x 0.5' concrete block over stone dated July 30, 1990  
 Measured East 2624.20' to fd. stone at N 1/4 corner of Sec. 27  
 Measured South 2653.56' to fd. iron over stone at W 1/4 corner  
     of Sec. 27  
 Measured East 1311.84' to fd. iron pieces  
 Fd. REM capped iron W.,SW 4.27'  
 PK in NW face power pole NE 81.41'  
 PK in S. face power pole NW 139.58'  
 Punch mark top of steel I-beam guard rail post SW 158.72'  
 C/L top tele. pedestal SE 42.10'
- (6) Kirk L. Van Order, P.C. survey dated Jan. 3, 1994  
 Fd. iron pipe in mon. box W.,SW 4.27'  
 Set capped iron using ties previously taken by me  
 Measure North 2638.51' to West 1/4 corner of Sec. 22, T.4N.,  
     R.14W.
- (7) Kirk L. Van Order, P.C. survey dated Aug. 9, 1994  
 Fd. capped iron  
 PK in NW face power pole NE 81.41'  
 PK in S. face power pole NW 139.58'  
 Punch mark top of steel  
 "I" beam guard rail post NW 158.72'  
 C/L top tele. pedestal SE 42.10'  
 Measured West 2622.18' to S 1/4 corner of Sec. 21, T.4N.,  
     R.14W.