

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Allegan (County) Located In: Corner Code #

1. Public Land Survey T 4N R 14 G-13
 T _____ R _____ SE Cor.
 T _____ R _____ Sec. 33
 T _____ R _____ SW Cor.
 T _____ R _____ Sec. 34
 Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

1995 DEC 14 PM 2:36
 FILED
 Register of Deeds Stamp & File Number

SURVEY &
 REMONUMENTATION
 APR 29 1996
 COMMISSION

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|----|----|----|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Kirk L. Van Order, in a field survey on April 3, 1995
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law, established, re-established, monumented, re-monumented, recovered, found as
 expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-13
 ●GLO set post corner Sec. 33 & 34
 Beech 8" N83°E 7 links
 Beech 7" N79°W 30 links
 Stake with stone on top
 ●T.O. Williams 1889 survey
 Fd. original stake - he then set a new stake with stone on top
 ●LCRC (L. 3, P. 369) David R. Greer, Nov. 1983
 (continued on back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13
 Fd. concrete monument by using ties listed in LCRC recorded in L.
 003, P. 369
 Monument approximately 1.8' below grade

And is accepted as a careful and faithful perpetuation of this
 position of the original corner.

Peer Group approved July 11, 1995.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 7-11-95
 COUNTY REP. Kirk L. Van Order

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13
 Set standard Allegan Co. Remon. monument (3/4" x 18" steel rod
 w/red cap #23520) above concrete monument
 Nail & Remon. tag W side power pole AZ. 352°47' 334.21'
 SW corner conc. wall to loading dock AZ. 20°33' 243.36'
 Nail & Remon. tag NE side power pole AZ. 134°11' 214.80'
 Nail & Remon. tag SE side power pole AZ. 258°20' 40.24'

Signed by [Signature] Date 12-13-95
 Surveyor's Michigan License No. 23520



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 PROFESSIONAL SURVEYOR

Section A (continued from Page 1)

G-13

- Using T.O. Williams 1889 survey measurement from G-12
 - Fd. stone and crockery
 - Under stone found wood post
 - Set conc. monument 4" x 36"
 - Power pole SE 214.75'
 - Power pole W,SW 41.26'
 - SW cor. house foundation N14°E 654.23'
 - NW cor. Sec. 3, T3N, R14W East 50.16'
- Kirk L. Van Order survey dated Mar. 16, 1989
 - Fd. conc. monument using LCRC ties dated Nov. 1983